

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
D 8 OVD SIN STR REPL 2010-45
Madison & St. Clair Counties
Sheet 3 of 16
Contract Number 46109

District 8
Schedule of Overhead Sign Structure Replacement

| | | | | | |
|--|-----------|-----------------|-----------------|------------|-----|
| Location No.: | 8-01 | State I.D. No.: | 8S082S013L002.5 | | |
| County: | St. Clair | Route: | il - 13 | M.P.: | 2.5 |
| | | | | Direction: | WB |
| Description of Work | Unit | Quantity | | | |
| REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN | EACH | 1.00 | | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| FURNISH & INSTALL SADDLE SHIM BLOCK | EACH | 4.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| FURNISH & INSTALL INTERNAL TRUSS DAMPER | EACH | 1.00 | | | |
| OVERHEAD SIGN STRUCTURE WALKWAY | FOOT | 139.00 | | | |
| OVERHEAD SIGN SUPPORT GROUT REPAIR | EACH | 4.00 | | | |
| REPLACE / TIGHTEN CLIP PER SIGN | EACH | 4.00 | | | |
| TIGHTEN SPLICE FLANGE | EACH | 1.00 | | | |

| | | | | | |
|--|-----------|-----------------|-----------------|------------|-----|
| Location No.: | 8-02 | State I.D. No.: | 8S082S015R007.7 | | |
| County: | St. Clair | Route: | IL - 15 | M.P.: | 7.7 |
| | | | | Direction: | EB |
| Description of Work | Unit | Quantity | | | |
| REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN | EACH | 1.00 | | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| FURNISH & INSTALL SADDLE SHIM BLOCK | EACH | 4.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| FURNISH & INSTALL INTERNAL TRUSS DAMPER | EACH | 1.00 | | | |
| OVERHEAD SIGN STRUCTURE WALKWAY | FOOT | 95.00 | | | |
| REPLACE U-BOLT | EACH | 4.00 | | | |
| OVERHEAD SIGN SUPPORT GROUT REPAIR | EACH | 4.00 | | | |
| REPLACE / TIGHTEN CLIP PER SIGN | EACH | 2.00 | | | |
| TIGHTEN SPLICE FLANGE | EACH | 1.00 | | | |

| | | | | | |
|--|-----------|-----------------|-----------------|------------|-----|
| Location No.: | 8-03 | State I.D. No.: | 8S082S015R007.6 | | |
| County: | St. Clair | Route: | IL - 15 | M.P.: | 7.6 |
| | | | | Direction: | EB |
| Description of Work | Unit | Quantity | | | |
| REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN | EACH | 1.00 | | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| FURNISH & INSTALL SADDLE SHIM BLOCK | EACH | 4.00 | | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| FURNISH & INSTALL INTERNAL TRUSS DAMPER | EACH | 1.00 | | | |
| REPLACE / TIGHTEN CLIPS PER SIGN | EACH | 2.00 | | | |
| OVERHEAD SIGN STRUCTURE WALKWAY | FOOT | 78.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| OVERHEAD SIGN SUPPORT GROUT REPAIR | EACH | 4.00 | | | |
| REPLACE U-BOLT | EACH | 15.00 | | | |
| REPAIR HANDRAIL LOCKING PIN CONNECTION | EACH | 4.00 | | | |

| | | | | | |
|--|---------|-----------------|----------------|------------|------|
| Location No.: | 8-04 | State I.D. No.: | 8S060270R013.2 | | |
| County: | Madison | Route: | I-270 | M.P.: | 13.2 |
| | | | | Direction: | EB |
| Description of Work | Unit | Quantity | | | |
| REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN | EACH | 1.00 | | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| OVERHEAD SIGN STRUCTURE WALKWAY | FOOT | 87.00 | | | |
| FURNISH & INSTALL INTERNAL TRUSS DAMPER | EACH | 1.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| OVERHEAD SIGN SUPPORT GROUT REPAIR | EACH | 4.00 | | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| FURNISH & INSTALL SADDLE SHIM BLOCK | EACH | 4.00 | | | |
| REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |

| | | | | | |
|--|-----------|-----------------|-----------------|------------|-----|
| Location No.: | 8-05 | State I.D. No.: | 8S082I055R003.7 | | |
| County: | St. Clair | Route: | I-55 | M.P.: | 3.7 |
| | | | | Direction: | NB |
| Description of Work | Unit | Quantity | | | |
| REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN | EACH | 1.00 | | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| FURNISH & INSTALL SADDLE SHIM BLOCK | EACH | 4.00 | | | |
| FURNISH & INSTALL INTERNAL TRUSS DAMPER | EACH | 1.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| OVERHEAD SIGN SUPPORT GROUT REPAIR | EACH | 4.00 | | | |
| OVERHEAD SIGN STRUCTURE WALKWAY | FOOT | 98.00 | | | |
| REPLACE U-BOLT | EACH | 4.00 | | | |
| REPLACE / TIGHTEN CLIPS PER SIGN | EACH | 2.00 | | | |
| REMOVE & REINSTALL VIDEO CAMERA & EQUIPMENT | EACH | 1.00 | | | |

| | | | | | |
|--|---------|-----------------|-----------------|------------|------|
| Location No.: | 8-06 | State I.D. No.: | 8S060S003R015.3 | | |
| County: | Madison | Route: | IL - 3 | M.P.: | 15.3 |
| | | | | Direction: | NB |
| Description of Work | Unit | Quantity | | | |
| REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN | EACH | 1.00 | | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| FURNISH & INSTALL INTERNAL TRUSS DAMPER | EACH | 1.00 | | | |
| FURNISH & INSTALL SADDLE SHIM BLOCK | EACH | 4.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| OVERHEAD SIGN STRUCTURE WALKWAY | FOOT | 52.00 | | | |
| OVERHEAD SIGN SUPPORT GROUT REPAIR | EACH | 4.00 | | | |
| REPLACE / TIGHTEN CLIPS PER SIGN | EACH | 1.00 | | | |
| REPLACE U-BOLT | EACH | 11.00 | | | |