

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

**BEAM 5**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+19.08	-7.67	684.86	684.86
⊘ Brg. W. Abut.	644+20.92	-7.67	684.87	684.87
A	644+30.92	-7.67	684.92	684.92
B	644+40.92	-7.67	684.96	684.96
C	644+50.92	-7.67	684.99	684.99
⊘ Brg. ⊙ Pier 1	644+62.42	-7.67	685.02	685.02
D	644+72.42	-7.67	685.04	685.06
E	644+82.42	-7.67	685.05	685.08
F	644+92.42	-7.67	685.06	685.10
G	645+02.42	-7.67	685.05	685.10
H	645+12.42	-7.67	685.05	685.08
I	645+22.42	-7.67	685.03	685.04
⊘ Brg. ⊙ Pier 2	645+29.08	-7.67	685.02	685.02
J	645+39.08	-7.67	684.99	684.99
K	645+49.08	-7.67	684.96	684.96
L	645+59.08	-7.67	684.92	684.92
⊘ Brg. E. Abut.	645+70.58	-7.67	684.86	684.86
Back E. Abut.	645+72.42	-7.67	684.85	684.85

**W.B. P.G.**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.76	-3.00	684.93	684.93
⊘ Brg. W. Abut.	644+20.60	-3.00	684.94	684.94
A	644+30.60	-3.00	684.99	684.99
B	644+40.60	-3.00	685.03	685.03
C	644+50.60	-3.00	685.06	685.06
⊘ Brg. ⊙ Pier 1	644+62.10	-3.00	685.09	685.09
D	644+72.10	-3.00	685.11	685.13
E	644+82.10	-3.00	685.12	685.16
F	644+92.10	-3.00	685.13	685.17
G	645+02.10	-3.00	685.13	685.17
H	645+12.10	-3.00	685.12	685.15
I	645+22.10	-3.00	685.10	685.12
⊘ Brg. ⊙ Pier 2	645+28.76	-3.00	685.09	685.09
J	645+38.76	-3.00	685.06	685.06
K	645+48.76	-3.00	685.03	685.03
L	645+58.76	-3.00	684.99	684.99
⊘ Brg. E. Abut.	645+70.26	-3.00	684.94	684.94
Back E. Abut.	645+72.10	-3.00	684.93	684.93

**BEAM 6**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.65	-1.33	684.96	684.96
⊘ Brg. W. Abut.	644+20.49	-1.33	684.97	684.97
A	644+30.49	-1.33	685.01	685.02
B	644+40.49	-1.33	685.05	685.06
C	644+50.49	-1.33	685.09	685.09
⊘ Brg. ⊙ Pier 1	644+61.99	-1.33	685.12	685.12
D	644+71.99	-1.33	685.14	685.16
E	644+81.99	-1.33	685.15	685.18
F	644+91.99	-1.33	685.16	685.20
G	645+01.99	-1.33	685.15	685.19
H	645+11.99	-1.33	685.15	685.18
I	645+21.99	-1.33	685.13	685.14
⊘ Brg. ⊙ Pier 2	645+28.65	-1.33	685.12	685.12
J	645+38.65	-1.33	685.09	685.09
K	645+48.65	-1.33	685.06	685.06
L	645+58.65	-1.33	685.02	685.02
⊘ Brg. E. Abut.	645+70.15	-1.33	684.96	684.96
Back E. Abut.	645+71.99	-1.33	684.95	684.95

DESIGNED	JMT
CHECKED	BLB
DRAWN	JMT
CHECKED	BLB

TOP OF SLAB ELEVATIONS - III  
STRUCTURE NO. 022-0033

<b>rjngroup</b> Excellence through Ownership 200 West Front Street Wheaton, IL 60187	SHEET NO. 6	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	27 SHEETS	311	10HB-R	Du Page	53	22
			CONTRACT NO. 60B92			
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT						