

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM 10

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+17.61	20.33	684.63	684.63
⊕ Brg. W. Abut.	644+19.45	20.33	684.64	684.64
A	644+29.45	20.33	684.68	684.69
B	644+39.45	20.33	684.73	684.73
C	644+49.45	20.33	684.76	684.76
⊕ Brg. ⊙ Pier 1	644+60.95	20.33	684.79	684.79
D	644+70.95	20.33	684.81	684.83
E	644+80.95	20.33	684.82	684.86
F	644+90.95	20.33	684.83	684.87
G	645+00.95	20.33	684.83	684.87
H	645+10.95	20.33	684.82	684.85
I	645+20.95	20.33	684.81	684.82
⊕ Brg. ⊙ Pier 2	645+27.61	20.33	684.79	684.79
J	645+37.61	20.33	684.77	684.77
K	645+47.61	20.33	684.74	684.74
L	645+57.61	20.33	684.70	684.70
⊕ Brg. E. Abut.	645+69.11	20.33	684.64	684.64
Back E. Abut.	645+70.95	20.33	684.63	684.63

BEAM 11

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+17.18	26.67	684.49	684.49
⊕ Brg. W. Abut.	644+19.02	26.67	684.50	684.50
A	644+29.02	26.67	684.55	684.55
B	644+39.02	26.67	684.59	684.59
C	644+49.02	26.67	684.63	684.63
⊕ Brg. ⊙ Pier 1	644+60.52	26.67	684.66	684.66
D	644+70.52	26.67	684.68	684.70
E	644+80.52	26.67	684.69	684.73
F	644+90.52	26.67	684.70	684.74
G	645+00.52	26.67	684.70	684.74
H	645+10.52	26.67	684.69	684.72
I	645+20.52	26.67	684.68	684.69
⊕ Brg. ⊙ Pier 2	645+27.18	26.67	684.66	684.66
J	645+37.18	26.67	684.64	684.64
K	645+47.18	26.67	684.61	684.61
L	645+57.18	26.67	684.57	684.57
⊕ Brg. E. Abut.	645+68.68	26.67	684.51	684.51
Back E. Abut.	645+70.52	26.67	684.50	684.50

BEAM 12

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+16.75	33.00	684.36	684.36
⊕ Brg. W. Abut.	644+18.59	33.00	684.37	684.37
A	644+28.59	33.00	684.42	684.42
B	644+38.59	33.00	684.46	684.46
C	644+48.59	33.00	684.49	684.49
⊕ Brg. ⊙ Pier 1	644+60.09	33.00	684.53	684.53
D	644+70.09	33.00	684.55	684.56
E	644+80.09	33.00	684.56	684.59
F	644+90.09	33.00	684.57	684.61
G	645+00.09	33.00	684.57	684.61
H	645+10.09	33.00	684.56	684.59
I	645+20.09	33.00	684.55	684.56
⊕ Brg. ⊙ Pier 2	645+26.75	33.00	684.53	684.53
J	645+36.75	33.00	684.51	684.51
K	645+46.75	33.00	684.48	684.48
L	645+56.75	33.00	684.44	684.44
⊕ Brg. E. Abut.	645+68.25	33.00	684.38	684.38
Back E. Abut.	645+70.09	33.00	684.37	684.37

DESIGNED	JMT
CHECKED	BLB
DRAWN	JMT
CHECKED	BLB

TOP OF SLAB ELEVATIONS - VI
STRUCTURE NO. 022-0033

rjngroup Excellence through Ownership 200 West Front Street Wheaton, IL 60187	SHEET NO. 9 27 SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		311	10HB-R	Du Page	53	25
			CONTRACT NO. 60B92			
		FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				