

INDEX OF SHEETS

SHEET NO DESCRIPTION

1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5-6	SCHEDULE
7-13	ALIGNMENT AND TIES
14-20	ROADWAY PLANS
21-22	STRUCTURAL PLANS
23	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)
24	ARTERIAL ROAD INFORMATION SIGN (TC-22)
25	SOLAR POWERED FLASHING BEACON DETAIL
26-42	CROSS SECTIONS

STATE STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
542101-02	REINFORCED CONCRETE END SECTIONS FOR PIPE CULVERTS 15" THRU 36" DIA. AT RIGHT ANGLES WITH ROADWAY
542546-01	FLUSH INLET BOX FOR MEDIAN
630001-08	STEEL PLATE BEAM GUARDRAIL
630101-08	GUARDRAIL MOUNTED ON EXISTING CULVERTS
630301-05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631011-00	TRAFFIC BARRIER TERMINAL, TYPE 2
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAIL
642001-01	SHOULDER RUMBLE STRIPS
667101-01	PERMANENT SURVEY MARKERS
701006-03	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701311-03	LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
701326-03	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH
701501-05	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701901-01	TRAFFIC CONTROL DEVICES

GENERAL NOTES

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATIONS IS REQUIRED)
2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITIES AND VILLAGES WITHIN THE PROJECT LIMITS.
3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
4. BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED - ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.
5. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO BEGINNING WORK.
6. THE CONTRACTOR SHALL DISPOSE OF ALL CUTTINGS AND SWEEP THE SHOULDER CLEAN PRIOR TO OPENING THE TRAFFIC LANE AND SHOULDER TO TRAFFIC. ALL DISPOSAL AND SWEEPING WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF SHOULDER RUMBLE STRIPS.
7. THE CONTRACTOR SHALL RESTRIPE THE EDGE LINES UPON COMPLETION OF THE MILLING OF THE RUMBLE STRIPS. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THERMOPLASTIC PAVEMENT MARKING - LINE 4".
8. ANY ADDITIONAL BRACING OR SHORING REQUIRED TO PERFORM THE WORK IS INCIDENTAL TO THE CONTRACT.
9. PLEASE CONTACT THE ROADSIDE DEVELOPMENT UNIT 72 HOURS IN ADVANCE OF SELECTIVE CLEARING AND TREE PROTECTION WORK AT (847) 705-4173. PURPLE RIBBON WILL BE USED TO DESIGNATE TREES AND SHRUBS TO BE SAVED. THE R.O.W. SHALL BE CLEARLY DELINEATED PRIOR TO THIS WORK. ORANGE RIBBON/SPRAY WILL BE USED TO DESIGNATE REMOVAL IN ADDITION TO ANY OF THE TREES LISTED IN THE SPECIAL PROVISION.
10. ANY SIGN LOCATED IN THE PUBLIC RIGHT-OF-WAY WHICH INTERFERES WITH CONSTRUCTION OF THE PROPOSED SHOULDER OR SIDESLOPE GRADING SHALL BE RELOCATED. THIS WORK SHALL BE INCLUDED IN THE PRICE FOR HMA BASE COURSE 6 1/4".
11. THE FOLLOWING RATES OF APPLICATION HAVE BEEN ASSUMED IN CALCULATING PLAN QUANTITIES:  
  
HOT-MIX ASPHALT SURFACE COURSE 112 LBS/SQ YD/INCH

FILE NAME = N:\PROJ\3366\3366\_20\Design\ProposedPlan\3366\_25-82-General Notes.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = ogutowski	DESIGNED DD	REVISED -
	DRAWN DD	REVISED -
PLOT SCALE = 1.0000' / IN.	CHECKED WBL	REVISED -
PLOT DATE = 12/16/2009	DATE 12/16/2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL 171  
IL 83 TO 104TH ST  
INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 3565	SECTION 2009-066 I	COUNTY COOK	TOTAL SHEETS 42	SHEET NO. 2
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H72	