

90% FED./10% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY SFTY-2A
CODE NO.	DESCRIPTION	UNIT		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	4,500	4,500
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	3,710	3,710
20101100	TREE TRUNK PROTECTION	EACH	10	10
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	10	10
20200100	EARTH EXCAVATION	CU YD	10,000	10,000
20201006	GRADING AND SHAPING SHOULDERS	UNIT	25	25
20800150	TRENCH BACKFILL	CU YD	50	50
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	16,000	16,000
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	12	12
25100630	EROSION CONTROL BLANKET	SQ YD	16,000	16,000
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	12	12
28000305	TEMPORARY DITCH CHECKS	FOOT	11,800	11,800
28000400	PERIMETER EROSION BARRIER	FOOT	25,600	25,600
28000500	INLET AND PIPE PROTECTION	EACH	1	1
28000510	INLET FILTERS	EACH	1	1
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	20,050	20,050
35501309	HOT-MIX ASPHALT BASE COURSE, 6 1/4"	SQ YD	16,100	16,100
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,250	2,250
44000100	PAVEMENT REMOVAL	SQ YD	2,250	2,250
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4,050	4,050
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,580	3,580
50102400	CONCRETE REMOVAL	CU YD	1	1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2
50200100	STRUCTURE EXCAVATION	CU YD	3	3
50300225	CONCRETE STRUCTURES	CU YD	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	180	180
54201273	PIPE CULVERTS, TYPE 2 RCCP 18"	FOOT	5	5
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	5	5
54213459	END SECTIONS 24"	EACH	1	1

• DENOTES SPECIALTY ITEM

90% FED./10% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY SFTY-2A
CODE NO.	DESCRIPTION	UNIT		
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1
58700300	CONCRETE SEALER	SQ FT	60	60
Δ 60255410	CATCH BASINS TO BE CLEANED	EACH	1	1
• 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	713	713
• 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	575	575
• 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	125	125
• 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4
• 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8
63200310	GUARDRAIL REMOVAL	FOOT	275	275
64200105	SHOULDER RUMBLE STRIP	FOOT	36,800	36,800
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
• 72000100	SIGN PANEL - TYPE 1	SQ FT	278	278
• 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	26	26
• 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	6	6
• 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	5	5
• 72500200	OBJECT MARKER - TYPE 2	EACH	12	12
• 72900100	METAL POST - TYPE A	FOOT	506	506
• 73000100	WOOD SIGN SUPPORT	FOOT	60	60
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37,000	37,000
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	30	30
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
* X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	4	4
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Δ Z0014700	CULVERT TO BE CLEANED	EACH	13	13
Z0064600	SELECTIVE CLEARING	ACRE	12	12

Δ- Non-participating

FILE NAME = N:\PROJ\3368\3368\_25\Design\ProposedPlan\3368\_25-43-50.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = ogutowski	DESIGNED DD	REVISED -
PLOT SCALE = 1/8" = 1' / IN.	DRAWN DD	REVISED -
PLOT DATE = 12/16/2009	CHECKED WBL	REVISED -
	DATE 12/16/2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL 171  
IL 83 TO 104TH ST  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 3565	SECTION 2009-066 I	COUNTY COOK	TOTAL SHEETS 42	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H72	

Rev.