



**NOTES:**

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

\* VARIOUS

FILE NAME =	USER NAME = geglent
W:\distatd\22x34\to22.dgn	

DESIGNED -	REVISED - R. MIRS 09-15-97
DRAWN -	REVISED - R. MIRS 12-11-97
PLOT SCALE = 50,000' / IN.	REVISED - T. RAMMACHER 02-02-99
CHECKED -	REVISED - C. JUCIUS 01-31-07
PLOT DATE = 1/4/2000	DATE -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ARTERIAL ROAD  
INFORMATION SIGN**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2009-072 I	LAKE	14	13
TC-22		CONTRACT NO. 60R82		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				