

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	URBAN 1000-2A					CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	URBAN 1000-2A				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	17	17					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3840	3840				
25200110	SODDING, SALT TOLERANT	SO YD	17	17					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15440	15440				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	80	80				
40600300	AGGREGATE (PRIME COAT)	TON	82	82					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	725	725				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	31	31					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	113	113				
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	833	833					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	20	20				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15440	15440				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	137	137					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	80	80				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	76	76					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	725	725				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1695	1695					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	113	113				
42001300	PROTECTIVE COAT	SO YD	23	23					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	20	20				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	20172	20172					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	120	120				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	102	102				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	450	450					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	66	66				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	122	122					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	162	162					X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	122	122					X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
55039700	STORM SEWERS TO BE CLEANED	FOOT	3750	3750													
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	16	16													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	9	9													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3													
67100100	MOBILIZATION	L SUM	1	1													
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4													

\* SPECIALTY ITEM