SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN)	CONSTRUCTION TYPE CODE: I000 ROADWAY	Y031-1F SIGNAL				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	371	371					
20400800	FURNISHED EXCAVATION	CU YD	23	23					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	20	20					
25200110	SODDING, SALT TOLERANT	SQ YD	20	20					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	101	101					
40600300	AGGREGATE (PRIME COAT)	TON	505	505					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	190	190					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5199	5199					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	845	845					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10586	10586					
42001300	PROTECTIVE COAT	SQ YD	878	878					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	126015	126015					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	120	120					
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	155	155					
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	65	65					
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	618	618					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	542	542					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	1355	1355					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	3522	3522					
44213100	PAVEMENT FABRIC	SQ YD	683	683					
44213200	SAW CUTS	FOOT	2817	2817					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	742	742					
55039700	STORM SEWERS TO BE CLEANED	FOOT	2476	2476					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1					
60253100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3					
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
60260100	INLETS TO BE ADJUSTED	EACH	1	1					
60264130	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	11	11					

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN 100% STATE)	CONSTRUCTION TYPE CODE: I000 ROADWAY	Y031-1F SIGNAL				
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1062.5	1062.5					
*	63100041	TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	1	1					
	63200310	GUARDRAIL REMOVAL	FOOT	25	25					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
	67100100	MOBILIZATION	L SUM	1	1					
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10					
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18360	18360					
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	328	328					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	70624	70624					
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2165	2165					
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	375	375					
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	926	926					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	735	735					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6120	6120					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	328	328					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	67320	67320					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2165	2165					
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	375	375					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	926	926					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	681	681					
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3304	3304					
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	54	54					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3030	3030					
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2697	2697					