

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I 000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I 000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	87	87					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	40	40					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
20400800	FURNISHED EXCAVATION	CU YD	160	160					70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	458	458					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11181	11181					
25000210	SEEDING, CLASS 2A	ACRE	0.09	0.09					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	108.9	108.9					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8	8					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37515	37515					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8	8					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	640	640					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8	8					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	520	520					
25100630	EROSION CONTROL BLANKET	SO YD	425	425					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	340	340					
25200110	SODDING, SALT TOLERANT	SO YD	33	33					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	108.9	108.9					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	48	48					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37515	37515					
40600300	AGGREGATE (PRIME COAT)	TON	240	240					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	640	640					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	90	90					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	520	520					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2375	2375					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	340	340					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	996	996					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	480	480					* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4836	4836					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	573	573					
42001300	PROTECTIVE COAT	SO YD	65	65					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	989	989					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	57568	57568					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	154.2	154.2					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200														
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	3585	3585														
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1152	1152														
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	864	864														
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	864	864														
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	240	240														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	686	686														
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	21	21														
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4														
63200310	GUARDRAIL REMOVAL	FOOT	200	200														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4														
67100100	MOBILIZATION	L SUM	1	1														

*Specialty Items