

SUMMARY OF QUANTITIES					URBAN CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES					URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	236	236						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	198	198					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	600	600						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	67645	67645					
25200110	SODDING, SALT TOLERANT	SO YD	600	600						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	262	262					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	58	58						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	201	201					
40600300	AGGREGATE (PRIME COAT)	TON	290	290						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1093	1093					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	23						78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	198	198					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	67645	67645					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1825	1825						78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	262	262					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1036	1036						78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	201	201					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6298	6298						78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	898	898					
42001300	PROTECTIVE COAT	SO YD	800	800						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	718	718					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	1097	1097						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	726	726					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	15014	15014						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3600	3600						X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SO YD	100	100					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	1589	1589						40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3636	3636					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	486	486						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	5118	5118					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	296	296						X4421000	PARTIAL DEPTH PATCHING	TON	672	672					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1890	1890						X4422030	PARTIAL DEPTH REMOVAL 3"	SO YD	4000	4000					
55039700	STORM SEWERS TO BE CLEANED	FOOT	950	950						X6060500	CORRUGATED MEDIAN REMOVAL	SO FT	200	200					
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2															
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	11	11															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	11	11															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	11	11															
60624600	CORRUGATED MEDIAN	SO FT	200	200															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7333	7333															

* SPECIALTY ITEM