



THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

- 15 EACH SIGNAL HEAD, 1-FACE, 3-SECTION
- 5 EACH SIGNAL HEAD, 1-FACE, 5-SECTION
- 1 EACH SIGNAL HEAD, 2-FACE, 3-SECTION
- 1 EACH SIGNAL HEAD, 2-FACE, 1-3 SECTION, 1-5 SECTION
- 16 EACH TRAFFIC SIGNAL BACKPLATE

**TRAFFIC SIGNAL NOTES**

1. REPLACEMENT OF EXISTING CONFIRMATION BEACONS WITH NEW L.E.D. CONFIRMATION BEACONS SHALL BE CONSIDERED INCIDENTAL TO THE PAY ITEM "UNINTERRUPTIBLE POWER SUPPLY".
2. ALL CABINET MODIFICATIONS AND/OR LOAD SWITCH REPLACEMENTS REQUIRED FOR PROPER OPERATION OF THE L.E.D. SIGNAL AND L.E.D. CONFIRMATION BEACON INDICATIONS TO THE SATISFACTION OF THE ENGINEER SHALL BE INCIDENTAL TO THE PAY ITEM "UNINTERRUPTIBLE POWER SUPPLY".
3. REMOVE EXISTING SIGNAL HEADS AND INSTALL NEW SIGNAL HEADS, L.E.D. REUSE ALL EXISTING CABLES.
4. INSTALL UNINTERRUPTIBLE POWER SUPPLY (UPS).

NOTE:  
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - BRD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TRAFFIC SIGNAL MODIFICATION PLAN IL ROUTE 59 AT IL ROUTE 62/68 SHEET 1 OF 2</b>			F.A.P. RTE. 339	SECTION 2009-088I	COUNTY COOK	TOTAL SHEETS 37	SHEET NO. 21
	PLOT SCALE = #SCALE#	DRAWN - OJT	REVISED -		SCALE: 1" = 20'	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT		CONTRACT NO. 60136	
	PLOT DATE = #DATE#	CHECKED - JJE	REVISED -									
		DATE - 11/20/09	REVISED -									