

SUMMARY OF QUANTITIES			100% STATE URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			100% STATE URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT		JOLIET RD. FAU 3562 ROADWAY 1000	55TH ST. FAU 1504 ROADWAY 1000				CODE NO.	ITEM		UNIT	JOLIET RD. FAU 3562 ROADWAY 1000	55TH ST. FAU 1504 ROADWAY 1000	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	55	55				70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	166	146	20			70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
40600300	AGGREGATE (PRIME COAT)	TON	827	727	100			70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8		8		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	318	280	38			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	37054	32649	4405		
40600895	CONSTRUCTING TEST STRIP	EACH	3	2	1			70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2083.5	1828.5	255		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1845	1780	65			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	99255	85315	13940		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	537	537				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8275	7090	1185		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	19761	17340	2421			70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1586	1586			
42001300	PROTECTIVE COAT	SQ YD	1196	1166	30			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1004	834	170		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	201649	176944	24705			70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1881	1661	220		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3585	3500	85			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5097	3627	1470		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	199	199				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2083.5	1828.5	255		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	119	119				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	99255	85315	13940		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	80	80				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8275	7090	1185		
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	745		745			* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1560	1560			
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	310		310			* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1004	834	170		
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	185		185			* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1881	1661	220		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	2363	2363				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2854	2409	445		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	2067	2067				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2343	1928	415		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	1477	1477				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	7403	5701	1702		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	105		105			X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	257	205.6	51.4		
55039700	STORM SEWERS TO BE CLEANED	FOOT	400		400			40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	8728	7708	1020		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	18	16	2			X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	2721	2721			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	169	168	1			Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	15	10		
60404950	FRAMES AND GRATES, TYPE 24	EACH	2		2			Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5				21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	597	583	14		
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	4	4				25200110	SODDING, SALT TOLERANT	SQ YD	597	583	14		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2										
67100100	MOBILIZATION	L SUM	1	0.5	0.5										
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1		1										

*Specialty Items

FILE NAME =	USER NAME = abebaw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.				
c:\pw_work\pwl\abebaw\0157545\010370-stp-plan.dgn		DRAWN -	REVISED -									*	2009-131 RS	COOK	51	3				
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -									SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD	ST. NO. 1	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 60142
PLOT DATE = 12/11/2009		DATE -	REVISED -																	