

INDEX OF SHEETS

| SHEET NO. | DESCRIPTION |
|-----------|-------------------------------------------------------------------------------------|
| 1 | COVER SHEET |
| 2 | INDEX, HIGHWAY STANDARDS, AND GENERAL NOTES |
| 3 | SUMMARY OF QUANTITIES |
| 4-5 | LOCATION MAPS |
| 6-15 | ROADWAY PLAN |
| 16 | DETAILS FOR DEPRESSED CURB AND GUTTER AND SHOULDER TREATMENT AT TBT TY 1 SPL (BD34) |
| 17 | ARTERIAL ROAD INFORMATION SIGNING (TC22) |

HIGHWAY STANDARDS

| STD. NO. | TITLE |
|-----------|-----------------------------------------------------------------------------|
| 630001-08 | STEEL PLATE BEAM GUARDRAIL |
| 630101-08 | GUARDRAIL MOUNTED ON EXISTING CULVERTS |
| 630201-06 | PCC/HMA STABILIZATION AT STEEL PLATE BEAM GUARDRAIL |
| 630301-05 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS |
| 631011-06 | TRAFFIC BARRIER TERMINAL TYPE 2 |
| 635006-03 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 635011-02 | REFLECTOR MARKER AND MOUNTING DETAILS |
| 701006-03 | OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE |
| 701326-03 | LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH |
| 701422-02 | LANE CLOSURE, MULTILANE, FOR SPEEDS ≥ 45 MPH TO 55 MPH |
| 701901-01 | TRAFFIC CONTROL DEVICES |

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK), 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED).
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND LOCAL AGENCIES.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED - ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.
- THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
- WHEN GUARDRAIL POSTS ARE PLACED BEHIND CONCRETE HEADWALLS, THE POSTS SHALL NOT BE PLACED TO BLOCK THE DRAINAGE OPENING.

| | | | | | | | | | | | |
|-------------|-----------------------------|------------|-----------|-----------------------------------------------------------|----------------------------------------------------------------------------------------------------------------|-------------------------|-------------|--------|--------------|-----------|---------------------------|
| FILE NAME = | USER NAME = .USER. | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | GUARDRAIL IMPROVEMENTS - NORTHERN WILL COUNTY INDEX OF SHEETS, HIGHWAY STANDARDS, AND GENERAL NOTES | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| #FILE# | PLOT SCALE = 50,0000' / IN. | DRAWN - | REVISED - | | | • | 2009-090GRR | WILL | 17 | 2 | |
| | PLOT DATE = 12/17/2009 | CHECKED - | REVISED - | | | • | VARIOUS | | | | CONTRACT NO. 60143 |
| | | DATE - | REVISED - | | | | | | | | ILLINOIS FED. AID PROJECT |
| | | | | SCALE: NTS | | SHEET NO. 1 OF 1 SHEETS | | STA. | | TO STA. | |