SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	Y031-F LAKE STREET	RIVER STREET	STOLP AVENUE	BROADWAY AVENUE	LINCOLN AVENUE	ROOT STREET	UNION STREET	OHIO STREET	INTERCONNECT
* 42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1047	486							561	
* 42400800	DETECTABLE WARNINGS	SQ FT	97	55							42	
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	145	58							87	
* 44000600	SIDEWALK REMOVAL	SQ FT	855	439							416	
* 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	145	58							87	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4									
67100100	MOBILIZATION	L SUM	1									
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1									
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1									
72000100	SIGN PANEL - TYPE 1	SQ FT	153.25	20.00		26.25		20.00	42.50		44.50	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	200							200		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	460	460								
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	34	34								
78300100	PAVEMENT MARKING REMOVAL	SQ FT	366	366								
80400100	ELECTRICAL SERVICE INSTALLATION	EACH	4			1		1	1		1	
81000600	CONDUIT IN TRENCH, 2" DIA.,GALVANIZED STEEL	FOOT	4146	716				26	207	57	47	3093
81000700	CONDUIT IN TRENCH, 2 1/2" DIA.,GALVANIZED STEEL	FOOT	382	57		81		84	43		117	
81001000	CONDUIT IN TRENCH, 4" DIA.,GALVANIZED STEEL	FOOT	335	39		51		55	91		99	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1373	138		41		24	61	43	23	1043
81018600	CONDUIT PUSHED, 2 1/2" DIA.,GALVANIZED STEEL	FOOT	125	55				39	24		7	
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	790	217		123		165	127		158	
81400100	HANDHOLE	EACH	12	3					1			8
81400300	DOUBLE HANDHOLE	EACH	4	1				1	1		1	
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2112.5			468.5		582	250		812	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5047	848		132		159	428	134	253	3093
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	5						1		4	
82500310	LIGHTING CONTROLLER TYPE, POLE MOUNTED, 240VOLT, 60 AMP	EACH	2					1			1	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	6	1	1	1	1		1	1		
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	3	1				1			1	
85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	3			1			1	1		
85900100	TRANSCEIVER	EACH	8									8
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3468	1026		425		496	528	459	534	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	10003.5	2023.5	223	1518.5		2103	1751	974	1410.5	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6689.5	801.5		1203.5		1413.5	1502.5		1768.5	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2253.5	803.5				386.5			1063.5	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3739.5	1809.5					756	1174		
87301615	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16 6 PAIR	FOOT	1677			349		552			776	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	575.5	221.5		48		94	41.5	84.5	86	
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2	1				1				
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	10	1		3		2	3		1	
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	2	2								
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4					1			3	
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1						1			
87702840	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 22 FT.	EACH	1								1	
87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1								1	
87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1								1	
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1						1			
87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1								1	
87704030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 20 FT. (SPECIAL)	EACH	1			1						

* SPECIALTY ITEMS

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / R.O.W. CHECKED / CADD FILE NAME — NOTE BOOK NO. — BY — DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTATNS CHKD — NOTE BOOK NO. — BY — DATE

FILE NAME = ...\trans\fin_dwg\690_5_sum01.dgn	USER NAME = _USER_	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN BAH	REVISED -				08-00270-00-TL	KANE	44 / 2
	PLOT SCALE = $SCALE$	CHECKED APS	REVISED -					CONTRACT NO. 63300	
	PLOT DATE = 12/17/2009	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	