SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	QUANTITY	SP PR	SPEC ITEM
28000500	INLET AND PIPE PROTECTION	EACH	2		
20800150	TRENCH BACKFILL	CU YD	3		
28000400	PERIMETER EROSION BARRIER	FOOT	60		
40600160	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1903		
40600300	AGGREGATE (PRIME COAT)	TON	19		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	726		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	710		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1452		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	1317		
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	179		
50105200	REMOVE EXISTING CULVERTS	EACH	1	*	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1		
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	28		
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1		
63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	138	*	*
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2		*
63200310	GUARDRAIL REMOVAL	FOOT	119		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	600		
72000100	SIGN PANEL - TYPE 1	SQ FT	18		
72900100	METAL POST - TYPE A	FOOT	42		
72900200	METAL POST - TYPE B	FOOT	16		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	147		*
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16832		*
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	480		*
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	656		*
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	13		*
78200400	GUARDRAIL Markers	EACH	13	*	*
X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	1	*	*
XX006425	RESTORATION	SQ YD	50	*	
67100100	MOBILIZATION	LSum	1		

SIGN PANEL TYPE 1 SCHEDULE

STA.	REF.	TYPE	DESCRIPTION	QUANTITY (SQ FT)
11+79	18' LT	W1-8L	CHEVRON LEFT	3.00
11+90	18' LT	W1-8L	CHEVRON LEFT	3.00
12+00	18' LT	W1-8L	CHEVRON LEFT	3.00
13+00	22' LT	W1-1	LEFT TURN ARROW	6.25
13+00	22' LT	W13-1	5 MPH ADVISORY	2.25
			TOTAL	17.5
PAY CODE: 72000100			USE	18

METAL POST - TYPE A SCHEDULE

STA.	REF.	TYPE	DESCRIPTION	QUANTITY (FEET)
11+79	18' LT	W1-8	CHEVRON LEFT	14
11+90	18' LT	W1-8	CHEVRON LEFT	14
12+00	18' LT	W1-8	CHEVRON LEFT	14
PAY CODE: 72900100			TOTAL	42

METAL POST - TYPE B SCHEDULE

STA.	REF.	TYPE	DESCRIPTION	QUANTITY (FEET)
13+00	22'LT	W1-1	LEFT TURN ARROW	16
		W1-13	5 MPH ADVISORY	
PAY CODE: 72900200			TOTAL	16

HOT-MIX ASPHALT SURFACE REMOVAL SCHEDULE

DRIVEWAY BUTT JOINT (INCLUDES SIDE STREETS)

STA	REF.	LENGTH (FEET)	AVG. WIDTH (FEET)	AREA (SQ. FT)	AREA (SQ. YD)
10+73	RT	8	18	144	16
12+64	LT	5	49	245	28
13+50	RT	10	26	260	29
15+20	LT	15	28	420	47
15+28	RT	15	25	375	42
24+80	LT & RT	15	93	1395	155
38+85	LT	15	115	1725	192
38+92	RT	15	98	1470	164
PAY CODE: XX007365				TOTAL	673

SURFACE REMOVAL, 3"

FROM	TO	LENGTH (FEET)	AVG. WIDTH (FEET)	AREA (SQ. FT)	AREA (SQ. YD)
10+50	12+00	150	26	3900	434
12+00	13+25	125	28	3500	389
13+25	13+85	60	28	1680	187
43+36	43+96	60	46	2760	307
PAY CODE: 44000198				TOTAL	1317

BUTT JOINT

STA	REF.	LENGTH (FEET)	AVG. WIDTH (FEET)	AREA (SQ. FT)	AREA (SQ. YD)
13+85		4.5	28	126	14
43+96		4.5	46	207	23
PAY CODE: 40600982				TOTAL	37

ROADWAY QUANTITIES SCHEDULE

FROM	WIDTH (FEET)	TO	WIDTH (FEET)	LENGTH (FEET)	AREA SQ. YD	LEVEL 1" (TON)	SURFACE 2" (TON)	SHLD WEDGE (TON)
10+50	24	12+00	28	150	433	24	49	0
12+00	28	13+25	28	125	389	22	44	0
13+25	28	13+50	28	25	78	4	9	1
13+50	28	21+60	34	810	2790	156	312	47
21+60	34	24+00	37	240	947	53	106	14
24+00	37	42+00	37	1800	7400	414	829	105
42+00	37	43+96	48	196	926	52	104	11
					PAY CODE	40600625	40603335	48102100
					TOTALS	726	1452	179

HAMPTON, LENZINI AND RENWICK, INC.
380 SHEPARD DRIVE · ELGIN, ILLINOIS 60123
847-697-6700 · www.hlrengineering.com
CIVIL ENGINEERS · STRUCTURAL ENGINEERS · LAND SURVEYORS

RAWSON BRIDGE ROAD
SUMMARY AND SCHEDULE OF QUANTITIES

SCALE: NONE | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3702	09-00003-00-SP	McHENRY	8	3
		CONTRACT NO. 63341		
FED. ROAD DIST. NO. 0	ILLINOIS	FED. AID PROJECT ARA-9003(476)		