



- PR HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
- PR HOT-MIX ASPHALT SURFACE REMOVAL, 1" PR POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50, 3/4"
- PR HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, 1 1/2"
- PAVEMENT PATCH (SEE SHEET 2, NOTE 7)

PR PAVEMENT MARKING LEGEND (TYP. ENTIRE SHEET)

THERMOPLASTIC PAVEMENT MARKING:

- ① CENTERLINE - 2 @ 4", YELLOW, 11" C-C
- ② EDGE LINE - 1 @ 4", WHITE
- ③ TURN LANE LINE - 1 @ 6", WHITE
- ④ STOP LINE - 1 @ 24", WHITE
- ⑤ PAINTED MEDIAN - 2 @ 4" YELLOW WITH 12" DIAGONALS @ 45 DEG., YELLOW, 75' C-C
- ⑥ LETTERS AND SYMBOLS - VARIOUS, WHITE

PR RAISED REFLECTIVE PAVEMENT MARKER (TYP. ENTIRE SHEET)

- ◆ ONE-WAY AMBER MARKER
- ◇ ONE-WAY CRYSTAL MARKER
- ◆ TWO-WAY AMBER MARKER

FILE NAME = 04-07_Plan Sheets_Powis LAPP
 PLOT DATE = 12/15/09

thomas engineering group
 thomas engineering group, llc
 238 south kentworth avenue
 suite 100
 oak park, il 60302
 phone: 708-533-1700

DESIGNED - BLP	REVISED -
DRAWN - BLP	REVISED -
CHECKED - DMM	REVISED -
DATE - 12/16/09	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

POWIS ROAD - IL RTE 64 (NORTH AVENUE) TO SMITH ROAD

PLAN SHEET

SCALE: 1" = 50'

STA. 6633+00 TO STA. 6637+66

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2530	09-00075-00-RS	DUPAGE	15	7
CONTRACT NO. 63350				
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT ARA-9003(403)	