

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	PARTICIPATING HSIP 90% FED 10% KANE COUNTY		NON-PARTICIPATING 100% KANE COUNTY
				1000-2A	RESURFACING ONLY	
20200100	EARTH EXCAVATION	CU YD	100	100		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2632	2078		554
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	231	231		
20800150	TRENCH BACKFILL	CU YD	17.1	17.1		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1471	1471		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27		
25200110	SODDING, SALT TOLERANT	SQ YD	1471	1471		
25200200	SUPPLEMENTAL WATERING	UNIT	9	9		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	152	152		
28000400	PERIMETER EROSION BARRIER	FOOT	375	375		
28000500	INLET AND PIPE PROTECTION	EACH	12	12		
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	693	693		
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	462	462		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	506	506		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1203	1203		
40600300	AGGREGATE (PRIME COAT)	TON	30	30		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	52	52		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	51.7	51.7		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1215	806		409
42001300	PROTECTIVE COAT	SQ YD	656	656		
44000100	PAVEMENT REMOVAL	SQ YD	13	13		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	7171	7171		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	3894			3894
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	534	534		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1948.5	1948.5		
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	3320	2202		1118
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	50	50.0		
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	25	25		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	13.5	13.5		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5	5		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	3	3		
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1		
60500060	REMOVING INLETS	EACH	8	8		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,24	FOOT	1968.0	1,968.0		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1098	1098		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11676	11676		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1811	1811		
Δ 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109.2	109.2		
Δ 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	11310.5	11310.5		
Δ 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	555.5	555.5		

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	PARTICIPATING HSIP 90% FED 10% KANE COUNTY		NON-PARTICIPATING 100% KANE COUNTY
				1000-2A	RESURFACING ONLY	
Δ 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	302.5	302.5		
Δ 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	56.0	56.0		
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	202.0	202		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2515	2515		
XZ191305	AGGREGATE SUBGRADE	TON	1958	1304		654
XD976500	END SECTIONS TO BE REMOVED	EACH	2	2		
28000305	TEMPORARY DITCH CHECKS	FOOT	60	60		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	137.5	137.5		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	11	11		
40600520	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1056	903		153
20013798	CONSTRUCTION LAYOUT	L SUM	1	1		

Δ INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED RDT	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>FABYAN PARKWAY SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN RDT	REVISED -			363	08-00370-00-SP	KANE	32	3
	PLOT SCALE = #SCALE#	CHECKED JAC	REVISED -			C-91-510-08		CONTRACT NO. 63416		
	PLOT DATE = #DATE#	DATE 12-08-09	REVISED -			ILLINOIS FED. AID PROJECT HSIP-9003 (056)				
				SCALE: NTS	SHEET NO. 3 OF 32 SHEETS	STA.	TO STA.			