



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 4, 2010

SUBJECT: FAU 1397 (St. Charles Road)  
Project M-9003(267)  
Section 09-00129-00-PV (Maywood)  
Cook County  
Contract No. 63428  
Item 172  
March 5, 2010 Letting  
Addendum (B)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

**Proposal – Index of Special Provisions, page 43 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott Stitt  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger  
Engineer of Project Development  
and Implementation

SPECIAL PROVISIONS  
ST. CHARLES ROAD IMPROVEMENTS PROJECT

INDEX

ITEM	PAGE
BITUMINOUS MATERIALS (PRIME COAT).....	25
INCIDENTAL HOT-MIX ASPHALT SURFACING.....	25
TOPSOIL FURNISH AND PLACE, 4".....	26
SODDING.....	26
RAILROAD TRACK REMOVAL.....	27
REMOVE AND RE-ERECT EXISTING SIGN.....	27
FENCE TO BE REMOVED AND REPLACED.....	27
TEMPORARY ACCESS (PRIVATE ENTRANCE).....	28
TEMPORARY ACCESS (COMMERCIAL ENTRANCE).....	28
TEMPORARY ACCESS (ROAD).....	29
TRAFFIC CONTROL – STAGE I.....	29
TRAFFIC CONTROL – STAGE II.....	30
TRAFFIC CONTROL AND PROTECTION FOR DETOUR ROUTE.....	31

**STREET LIGHTING SPECIAL PROVISIONS**

GENERAL ELECTRICAL REQUIREMENTS.....	32
MAINTENANCE OF LIGHTING SYSTEMS.....	33
WIRE AND CABLE.....	35
UNDERGROUND RACEWAYS.....	37
EXPOSED RACEWAYS.....	38
GROUND ROD.....	40
ELECTRIC SERVICE INSTALLATION.....	41
NOTIFICATION OF STATE ELECTRICAL MAINTENANCE CONTRACTOR.....	41
GROUNDING OF LIGHTING SYSTEM.....	42
ELECTRIC UTILITY SERVICE CONNECTION.....	42
LUMINAIRE, METAL HALIDE, HORIZONTAL MOUNT 250 WATT.....	42
LIGHTING CONTROLLER, SPECIAL.....	42
UNIT DUCT.....	43
LUMINAIRE (BEO).....	43
IDOT DISTRICT 1 LUMINAIRE PERFORMANCE TABLE #1.....	50

**TRAFFIC SIGNAL SPECIAL PROVISIONS**

TRAFFIC SIGNAL SPECIFICATIONS.....	51
SECTION 720 SIGNING	
MAST ARM SIGN PANELS.....	51
DIVISION 800 ELECTRICAL	
SUBMITTALS.....	51

Revised 3-4-10

- 1068.01(b) Delete Article 1068.01(b) (2) Double Door Enclosure and 1068.01(b) (3) Wall Mount Enclosure
- 1068.01(c) Delete Article 1068.01(c) (1) Unfinished Enclosures. The color of the finish coat for the control cabinet shall be Durandonic dark bronze. Samples of the finish shall be submitted to the Engineer for approval before ordering.
- 1068.01(e) Delete Article 1068.01(e) (1) Time Switch. The Control Center shall be subject to the inspection and approval of the Commonwealth Edison Company, after which, if satisfactory, the electrical cables or wires of Commonwealth Edison Company shall be connected with the circuits of the lighting system at the Control Center.

Revise the first sentence of Article 1068.01(e)(4) of the Standard Specifications to read:

“Contactors shall be electrically operated, mechanically held as specified, with the number of poles required for the service and with operating coil voltage as indicated. The contactor shall have an in-line drive operating mechanism.”

Basis of Payment: This item shall be paid for at the Contract unit price per Each for LIGHTING CONTROLLER, SPECIAL, which price shall include service cabinet, foundations and erections, hardware and all necessary electrical components as described above or as shown on the Plans, installation of appurtenant components, making the connections with Commonwealth Edison facilities, and all equipment, material and labor necessary to complete the work in accordance with the requirements of the Contract Documents.

**UNIT DUCT, 600V, 3 -1C NO.6, 1/C NO.8 GROUND, (XLP -TYPE USE), 1" DIA. POLYETHYLENE**

Work shall be in accordance with Section 816 of the Standard Specifications. The Contractor is to be aware that 10,000 feet of the quantity for this item is to be installed by the bore and pull method as identified in Article 816.03 (c) and that the cost of the bore and pull is to be included in the cost of this item. Additionally, the cost of any excavation, disposal of excavated material and restoration for the exposing of any utilities that could possibly be in conflict with the proposed unit duct path shall be considered included in the cost of this item.

Basis of Payment: This item shall be paid for at the Contract unit price per Foot for UNIT DUCT, 600V, 3 -1C NO.6, 1/C NO.8 GROUND, (XLP -TYPE USE), 1" DIA. POLYETHYLENE which price shall include all equipment, material and labor necessary to complete the work in accordance with these specifications.

Revised 3-9-10