

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	J000-2A 80% FEDERAL 20% LOCAL	Y-031-IF 80% FEDERAL 20% LOCAL	Y-030-IE 80% FEDERAL 20% LOCAL
20200100	EARTH EXCAVATION	CU YD	6,580	6,580	0	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	7,000	7,000	0	0
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	7,000	7,000	0	0
20800150	TRENCH BACKFILL	CU YD	161	161	0	0
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,000	4,000	0	0
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	75	75	0	0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	75	75	0	0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	75	75	0	0
* 25200100	SODDING	SQ YD	4,000	4,000	0	0
25200200	SUPPLEMENTAL WATERING	UNIT	100	100	0	0
28000510	INLET FILTERS	EACH	79	79	0	0
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	29,322	29,322	0	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	209	209	0	0
40600300	AGGREGATE (PRIME COAT)	TON	3	3	0	0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	75	75	0	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	400	400	0	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	150	150	0	0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	95	95	0	0
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	29,500	29,500	0	0
42101300	PROTECTIVE COAT	SQ YD	35,570	35,570	0	0
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	1,350	1,350	0	0
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	14	14	0	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	23,000	23,000	0	0
42400800	DETECTABLE WARNINGS	SQ FT	720	720	0	0
44000100	PAVEMENT REMOVAL	SQ YD	29,500	29,500	0	0
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1,400	1,400	0	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,300	1,300	0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12,500	12,500	0	0
44000600	SIDEWALK REMOVAL	SQ FT	27,000	27,000	0	0
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	39	39	0	0
56106300	ADJUSTING WATER MAIN 6"	FOOT	295	295	0	0
56106600	ADJUSTING WATER MAIN 12"	FOOT	75	75	0	0
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	18	18	0	0
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND BOX	EACH	18	18	0	0
56500800	DOMESTIC WATER SERVICE BOXES	EACH	80	80	0	0
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	3	3	0	0
60213800	RESTRICTED DEPTH CATCH BASINS, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	32	32	0	0
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	37	37	0	0
60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6	0	0
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	0	0
60249400	VALVE BOXES 6"	EACH	3	3	0	0
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2	0	0
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	31	31	0	0
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1	1	0	0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	70	70	0	0
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	76	76	0	0
60500040	REMOVING MANHOLES	EACH	1	1	0	0
60500050	REMOVING CATCH BASINS	EACH	7	7	0	0
60500060	REMOVING INLETS	EACH	60	60	0	0
60600905	CONCRETE CURB, TYPE B (MODIFIED)	FOOT	130	130	0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	11,800	11,800	0	0
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	500	500	0	0
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,000	1,000	0	0
67100100	MOBILIZATION	L SUM	1	1	0	0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	0	0
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	18,440	18,440	0	0
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	40	40	0	0
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4	FOOT	14,960	14,960	0	0
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24	FOOT	40	40	0	0
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	25	25	0	0
* 72000100	SIGN PANEL - TYPE 1	SQ FT	521	521	0	0
* 72900100	METAL POST - TYPE A	FOOT	565	565	0	0
* 72900200	METAL POST - TYPE B	FOOT	259	259	0	0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	680	680	0	0
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	400	400	0	0
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	13,598	13,598	0	0
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1,780	1,780	0	0
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	816	816	0	0
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	518	518	0	0
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	0	0	1
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1,070	0	1,070	0
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	73	0	73	0
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	20	0	20	0
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1,183	0	133	1,050

* DENOTES SPECIALTY ITEMS

Drawing file: W:\Projects\56502290 - St. Charles Rd\00_Sum_Quantities.dwg Dec: 22, 2009 - 5:53pm

HANCOCK ENGINEERING
 Civil Engineers
 Municipal Consultants
 Established 1911

9911 Riverchase Road
 Westchester, Illinois 60594-2790
 Phone: 708.662.0200
 Fax: 708.662.0212

USER NAME -	DESIGNED - MK/SBC	REVISED -
PLOT SCALE -	DRAWN - MK/LEV	REVISED -
PLOT DATE -	CHECKED - SBC/JGMV	REVISED -
	DATE - 11-30-09	REVISED - IDOT REV. 12-22-09

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1397	09-00129-00-PV	COOK	103	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63428	
			M-9003 (267)	

BOOK NOS. 1470, 1482, 1486 E.H.E. PROJECT NO. 56502290