

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
* A2006518	TREE, ULMUS PARVIFOLIA (LACEBARK ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	2
* A2007624	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 3" CALIPER BALLED AND BURLAPPED	EACH	2
* B2005720	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2.5" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5
X0322102	TEMPORARY SIDEWALK RAMP	EACH	20
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	180
X0323927	MAINTENANCE OF LIGHTING SYSTEM	EACH	1
X0444100	BENCHES	EACH	6
* X0539800	TREE GRATES	EACH	34
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	21
XX000959	TRASH RECEPTACLES	EACH	6
XX003535	AGGREGATE BASE COURSE, TYPE B 2"	SQ YD	2,266
XX004688	BRICK PAVER SIDEWALK	SQ FT	4,912
* A200652A	TREE QUERCUS BICOLOR (SWAMP WHITE OAK), 3" CALIPER, BALLED & BURLAPPED	EACH	1
* A2002490	TREE, CARPINUS BETULUS FASTIGIATA, (COLUMNAR EUROPEAN HORNBEAM), 3.5" CALIPER, BALLED AND BURLAPPED	EACH	3
* A2006726	TREE, QUERCUS MACROCARPA (BUR OAK), 3" CALIPER, BALLED AND BURLAPPED	EACH	2
Z0019600	DUST CONTROL WATERING	UNIT	5
* 21101655	TOPSOIL FURNISH AND PLACE, 14"	SQ YD	183
XX008277	PORTLAND CEMENT CONCRETE UNDERLAYMENT, 5 INCH	SQ YD	546
X0321524	CHIMNEY SEAL	EACH	2
* XX008278	UNIT DUCT, 600V, 6-1/C NO.6, 1/C NO.8 GROUND, (EPR-TYPE RHW), 1 1/2" DIA. POLYETHYLENE	FOOT	4,721
* XX008279	UNIT DUCT, 600V, 6-1/C NO.4, 1/C NO.8 GROUND, (EPR-TYPE RHW), 2" DIA. POLYETHYLENE	FOOT	1,051
* XX008280	ORNAMENTAL STREET LIGHTING UNIT - SINGLE TEARDROP FIXTURE	EACH	41
* XX008281	ORNAMENTAL STREET LIGHTING UNIT - SINGLE ACORN FIXTURE	EACH	41

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 ALL RIGHTS RESERVED. EXPIRES 4/30/2011
 LICENSE NO. 194-00197-0001 EXPIRES 4/30/2011
 11/30/2009 10:54 AM
 \\C:\p\ba\woodman.com\p\ofac\15\c\y1st\l\skok\091028\CADD\SURVEY DRAWINGS\091028-500.dwg



DESIGNED -	DJS	REVISED -	IDOT REVIEW 11/23/09
DRAWN -	RKM/CJC/MAC	REVISED -	
CHECKED -	MDW	REVISED -	IDOT REVIEW 6/3/09
DATE -	10-16-2009	FILE -	091028-500.sht

VILLAGE OF SKOKIE, ILLINOIS
U.S. ROUTE 41 (SKOKIE BOULEVARD)
STREETScape IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	09-00283-00-LS	COOK	27	6
C-91-285-10			CONTRACT NO. 63430	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003(547)				