

SIDEWALK SCHEDULE

STATION BEGIN	STATION END	SIDEWALK REMOVAL SQ FT	DETECTABLE WARNINGS SQ FT	PCC SIDEWALK 5 INCH SQ FT	AGGREGATE BASE COURSE TYPE B, 2" SQ YD	BRICK PAVER SIDEWALK SQ FT	PCC UNDERLAYMENT 5 INCH SQ YD	SUB-BASE GRANULAR MATERIAL TYPE B, 6" SQ YD
10+40 RT	12+00 RT (ALLEY)	1,248	8	571	63	154	17	17
12+00 RT (ALLEY)	16+82 RT (KEENEY ST)	2,441	32	2,698	300	704	78	78
16+82 RT (KEENEY ST)	23+44 RT (CLEVELAND ST)	4,701	34	5,331	592	1,344	149	149
23+44 RT (CLEVELAND ST)	30+02 RT (MADISON ST)	3,970	32	4,357	484	958	106	106
24+33 LT	33+33 LT (WASHINGTON ST)	3,958	34	5,778	642	1,368	152	152
30+02 RT (MADISON ST)	33+33 RT (WASHINGTON ST)	1,714	54	1,659	184	384	43	43
		18,032 SQ FT	194 SQ FT	20,394 SQ FT	2,266 SQ YD	4,912 SQ FT	546 SQ YD	546 SQ YD

DRIVEWAY SCHEDULE

STATION	EXISTING DRIVEWAY APRON TYPE	RESIDENTIAL OR COMMERCIAL	EXISTING WIDTH AT ROW FOOT	EXISTING WIDTH AT CURB FOOT	LENGTH FOOT	EXISTING DRIVEWAY PAVEMENT AREA SQ YD	DRIVEWAY PAVEMENT REMOVAL SQ YD	PROPOSED WIDTH AT ROW FOOT	PROPOSED WIDTH AT CURB FOOT	PROPOSED LENGTH OF DRIVEWAY FOOT	PROPOSED DRIVEWAY PAVEMENT AREA SQ YD	PCC DRIVEWAY PAVEMENT 8 INCH (SPECIAL) SQ YD	SUB-BASE GRANULAR MATERIAL TYPE B, 4 INCH SQ YD
SKOKIE BOULEVARD													
11+13 RT	CONCRETE	COMMERCIAL	23	23	2	13	13	26	42	10	46	46	46
11+64 RT	CONCRETE	COMMERCIAL	23	23	2	13	13	26	42	10	46	46	46
12+90 RT	CONCRETE	COMMERCIAL	23	35	9	37	37	27	43	9	43	43	43
13+52 RT	CONCRETE	COMMERCIAL	17	22	9	28	28	17	33	9	33	33	33
14+27 RT	CONCRETE	COMMERCIAL	26	39	9	41	41	27	43	9.5	45	45	45
20+25 RT	CONCRETE	COMMERCIAL				-	-	18	34	10	37	37	37
24+16 LT	CONCRETE	COMMERCIAL	27	29	10	39	39	30	46	9.5	48	48	48
24+55 RT	CONCRETE	COMMERCIAL	12	19	10	25	25	0	0	0	0	0	0
24+77 LT	CONCRETE	COMMERCIAL	42	45	10	54	54	42	58	9	58	58	58
25+55 LT	CONCRETE	COMMERCIAL	12	17	10	24	24	12	28	9.5	29	29	29
25+60 RT	CONCRETE	COMMERCIAL	21	28	10	36	36	20	36	10	29	29	29
26+23 RT	CONCRETE	COMMERCIAL	32	40	10	50	50	33	49	9.5	51	51	51
27+03 RT	CONCRETE	COMMERCIAL	33	41	10	51	51	33	49	9.5	51	51	51
27+45 LT	CONCRETE	COMMERCIAL				-	-	14	30	9	30	30	30
27+78 RT	CONCRETE	COMMERCIAL				-	-	16	32	10	35	35	35
27+89 LT	CONCRETE	COMMERCIAL				-	-	22	38	9.5	40	40	40
28+48 LT	CONCRETE	COMMERCIAL				-	-	23	39	9.5	41	41	41
30+46 LT	CONCRETE	COMMERCIAL	26	28	9	35	35	26	42	9	42	42	42
30+68 RT	CONCRETE	COMMERCIAL	20	29	5	24	24	20	36	9	36	36	36
31+05 RT	CONCRETE	COMMERCIAL	17	23	4	17	17	16	32	9.5	33	33	33
31+87 RT	CONCRETE	COMMERCIAL	19	30	4	19	19	17	33	9.5	34	34	34
32+20 RT	CONCRETE	COMMERCIAL	18	33	4	20	20	14	30	9.5	31	31	31
TOTALS						526 Sq. Yd.	526 Sq. Yd.				838 Sq. Yd.	838 Sq. Yd.	838 Sq. Yd.

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 LICENSE NO. 184-00121 / EXPIRES 4/30/2011
 11/20/2009 11:31:45 AM
 S:\SKOKIE\09028\CADD-SURVEY\DRAWINGS\UDONS\09028-Schedule.sht



DESIGNED -	DJS	REVISED -	IDOT REVIEW 11/23/09
DRAWN -	RKM/CJC/MAC	REVISED -	
CHECKED -	MDW	REVISED -	
DATE -	10-16-2009	FILE -	091028-Schedule.sht

**VILLAGE OF SKOKIE, ILLINOIS
U.S. ROUTE 41 (SKOKIE BOULEVARD)
STREETSCAPE IMPROVEMENTS**

SCHEDULE OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	09-00283-00-LS	COOK	27	9
C-91-285-10		CONTRACT NO. 63430		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003647				