

SCHEDULE OF QUANTITIES

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"

FOOT	LOCATION
US 20	
380	Sta 99+27 - 114+33 WB, 10' DASH / 30' SKIP
380	Sta 99+27 - 114+33 EB, 10' DASH / 30' SKIP
760	TOTAL

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION
US 20	
265	Sta 105+91 - 108+56 EB LEFT TURN LANE LINE
265	TOTAL

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION
245	Sta 99+27 - 114+33 CENTER YELLOW DIAGONALS
245	TOTAL

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION
US 20	
12	Sta 108+78 , 40' LT. CAMILLUS DRIVE STOP BAR
12	TOTAL

78005110 EPOXY PAVEMENT MARKING, LINE - 4"

FOOT	LOCATION
US 20	
5,000.0	Sta 82+88 - 133+55 AS NEEDED & DIRECTED BY THE RESIDENT FOR REPLACE/MENT FOLLOWING EACH MOT STAGE ON EXISTING PCC PAVEMENT
5,000	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
US 20	
48	Sta 99+27 - 114+33 EB TWO-WAY AMBER
37	Sta 99+27 - 114+33 WB TWO-WAY AMBER
19	Sta 99+27 - 114+33 EB ONE-WAY CRYSTAL
19	Sta 99+27 - 114+33 ONE-WAY CRYSTAL
123	TOTAL

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION
US 20	
5	Sta 104+97 - 108+59.5 EB
3	Sta 105+97 - 108+22 WB
8	TOTAL

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION
US 20	
1	Sta 104+47 EB GUARDRAIL TERMINATION
1	Sta 108+02 EB GUARDRAIL TERMINATION
1	Sta 105+44 WB GUARDRAIL TERMINATION
1	Sta 108+72 WB GUARDRAIL TERMINATION
4	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	DESCRIPTION
US 20		
108.33	Sta 76+28.0 - 82+88.0	STAGE 1 14' RT (13 X 25' DASH)
108.33	Sta 138+00.0 - 144+60.0	STAGE 2 45' LTT TO 20' LT (13 X 25' DASH)
293.33	Sta 95+05.0 - 10+35.0	STAGE 3 2' LT
220.00	Sta 97+25.0 - 103+85.0	STAGE 3 2' RT
125.00	Sta 103+85.0 - 111+55.0	STAGE 3 14' RT (15 X 25' DASH)
246.67	Sta 104+15.0 - 111+55.0	STAGE 3 26' RT
220.00	Sta 113+75.0 - 120+35.0	STAGE 3 2' LT
193.33	Sta 111+55.0 - 117+35.0	STAGE 3 2' RT
220.00	Sta 126+95.0 - 133+55.0	STAGE 3 33' LTT TO 43' LT
5.00	Sta 97+10.0 - 97+25.0	STAGE 4 2' RT
67.50	Sta 103+85.0 - 105+87.5	STAGE 4 2' LT
67.50	Sta 103+85.0 - 105+87.5	STAGE 4 2' RT
120.00	Sta 105+90.0 - 109+50.0	STAGE 4 26' LTT
125.00	Sta 105+90.0 - 109+50.0	STAGE 4 14' LTT (15 X 25' DASH)
141.67	Sta 109+50.0 - 113+75.0	STAGE 4 2' LT
68.33	Sta 109+50.0 - 111+55.0	STAGE 4 2' RT
68.33	Sta 117+35.0 - 119+40.0	STAGE 4 2' RT
220.2	Sta 99+27 - 105+88	EDGE LINE, 26" LT
162.7	Sta 99+27 - 104+15	EDGE LINE, 26" RT
225.0	Sta 99+27 - 105+88	14' LT (27 X 25' DASH)
158.3	Sta 99+28 - 103+85	14' RT (19 X 25' DASH)
185.7	Sta 105+88 - 108+66	DOUBLE YELLOW (x2) 2' RT, LT
161.0	Sta 109+50 - 114+33	EDGE LINE, 26" LT
166.7	Sta 109+50 - 114+33	14' LT (20 X 25' DASH)
100.0	Sta 111+55 - 114+33	14' RT (12 X 25' DASH)
92.7	Sta 111+55 - 114+33	EDGE LINE, 26" RT
3,871.0	TOTAL	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
US 20	
40	Sta 88+27.0 - 126+56 ESTIMATED QUANTITY AS NEEDED & DIRECTED BY THE RESIDENT
40	TOTAL

X0323988 TEMPORARY SOIL RETENTION SYSTEM

SQ FT	LOCATION
US 20	
989	Sta 107+67.5
989	TOTAL

Z0005400 BREAKER RUN CRUSHED STONE

TON	LOCATION
US 20	
445	Sta 107+67.5
445	TOTAL

Z0024476 FLEXIBLE DELINEATOR MAINTENANCE

EACH	LOCATION
US 20	
20	Sta 100+75 - 113+50 MOT STAGE 3, AS DIRECTED BY THE RESIDENT
10	Sta 104+25 - 110+20 MOT STAGE 4, AS DIRECTED BY THE RESIDENT
30	TOTAL

Z0024478 FLEXIBLE DELINEATOR

EACH	LOCATION
US 20	
26	Sta 100+75 - 113+50 MOT STAGE 3
12	Sta 104+25 - 110+20 MOT STAGE 4
38	TOTAL