

SUMMARY OF QUANTITIES

ROADWAY
J000-2A
80% FED 20%
STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	35673
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	600
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	60
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14368
70400100	TEMPORARY CONCRETE BARRIER	FOOT	10250
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5000
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	118
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4816
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	30
A2005114	TREE, JUGLANS NIGRA (BLACK WALNUT), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	30
A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	30
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	30
A2007114	TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	30
B2002614	TREE, MALUS ADAMS (ADAMS CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	35
B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	35
B2005214	TREE, MALUS SUTYZAM (SUGAR TYME CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	35
C2001748	SHRUB, CORNUS SERICEA CARDINAL (CARDINAL REDOSIER DOGWOOD), 4' HEIGHT, BALLED AND BURLAPPED	EACH	35
D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	20
X0322288	MEDIAN CLOSURE	EACH	1
X0322352	SEEDING MOBILIZATION	EACH	2
X0323660	DROP BOX NO. 1	EACH	1
X0326682	UPGRADE EXISTING WEATHER STATION	L SUM	1
X0712400	TEMPORARY PAVEMENT	SQ YD	916
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	586
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	691
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	LSUM	1
X7800610	URETHANE PAVEMENT MARKING-LINE 4"	FOOT	9400
X7800630	URETHANE PAVEMENT MARKING-LINE 6"	FOOT	1180
X8410105	TEMPORARY LIGHTING SYSTEM	EACH	2
Z0013798	CONSTRUCTION LAYOUT	LSUM	1
Z0014800	CULVERT TO BE CLEANED	FOOT	148
Z0023600	FILLING EXISTING CULVERTS	EACH	2
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	3

* SPECIALTY ITEMS
† NON PARTICIPATING 100% STATE

▲ NON-PARTICIPATING
100% STATE

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw_work\pwsdot\cushmanbw\d0117386\022808-sht-schedule.dgn	2808-sht-schedule.dgn	DRAWN -	REVISED -			301	31T	JO DAVIESS	160	5	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64D92					
PLOT DATE = Wed Dec 09 13:59:13 2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.