

SCHEDULE OF QUANTITIES

50104400 CONCRETE HEADWALL REMOVAL

EACH	LOCATION	REMARK'S
1	LT. STA. 257 + 31	
1	LT. STA. 264 + 95	
2	TOTAL	

51500100 NAME PLATES

EACH	LOCATION	REMARK'S
1	STA. 249 + 74	
1	TOTAL	

542A1081 PIPE CULVERTS, CLASS A, TYPE 2 36"

FOOT	LOCATION	REMARK'S
84	STA. 241 + 91	
84	TOTAL	

542A1117 PIPE CULVERTS, CLASS A, TYPE 2 72"

FOOT	LOCATION	REMARK'S
180	STA. 249 + 74	112' LT & 68' RT @ 52° SKEW
180	TOTAL	

54213681 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"

EACH	LOCATION	REMARK'S
1	RT. STA. 241 + 91	
1	TOTAL	

54213717 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 72"

EACH	LOCATION	REMARK'S
1	LT. STA. 249 + 74	
1	TOTAL	

60100060 CONCRETE HEADWALL FOR PIPE DRAINS

EACH	LOCATION	REMARK'S
1	RT. STA. 232 + 00	
1	RT. STA. 235 + 00	
2	LT & RT. STA. 238 + 00	
2	LT & RT. STA. 241 + 00	
2	LT & RT. STA. 243 + 00	
1	RT. STA. 246 + 00	
1	LT. STA. 250 + 00	
1	RT. STA. 251 + 00	
1	LT. STA. 253 + 00	
1	LT. STA. 256 + 00	
1	LT. STA. 259 + 00	
1	LT. STA. 262 + 00	
1	LT. STA. 265 + 00	
1	LT. STA. 268 + 00	
1	RT. STA. 270 + 00	
1	RT. STA. 273 + 00	
1	RT. STA. 276 + 00	
1	LT. STA. 277 + 00	
21	TOTAL	

60107600 PIPE UNDERDRAINS, 4"

FOOT	LOCATION	REMARK'S
2162	RT. STA. 232 + 00 TO 253 + 62	
748	LT. STA. 237 + 00 TO 244 + 49	
2311	LT. STA. 249 + 64 TO 272 + 75	
893	RT. STA. 270 + 07 TO 279 + 00	
195	LT. STA. 276 + 80 TO 278 + 75	
6310	TOTAL	

60108100 PIPE UNDERDRAINS 4" (SPECIAL)

FOOT	LOCATION	REMARK'S
20	RT. STA. 232 + 00	
16	RT. STA. 235 + 00	
10	LT. STA. 238 + 00	
13	RT. STA. 238 + 00	
10	LT. STA. 241 + 00	
13	RT. STA. 241 + 00	
10	LT. STA. 243 + 00	
13	RT. STA. 243 + 00	
15	RT. STA. 246 + 00	
10	LT. STA. 250 + 00	
14	RT. STA. 251 + 00	
10	LT. STA. 253 + 00	
10	LT. STA. 256 + 00	
10	LT. STA. 259 + 00	
10	LT. STA. 262 + 00	
10	LT. STA. 265 + 00	
10	LT. STA. 268 + 00	
15	RT. STA. 270 + 00	
15	RT. STA. 273 + 00	
15	RT. STA. 276 + 00	
10	LT. STA. 277 + 00	
259	TOTAL	

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -
or\pwork\pwork\cushmanbw\d0117386\022808-sh-t-schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	31T	JO DAVIESS	160	18
CONTRACT NO. 64D92				
ILLINOIS FED. AID PROJECT				