

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	1000-1A	
			90% Fed/ 10% State	TOTAL QUANTITY
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH		2
54213681	PREACST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH		1
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT		4
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT		8
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT		756
63500310	REMOVE AND REINSTALL DELINEATORS	EACH		4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO		3
67100100	MOBILIZATION	L SUM		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM		1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA		10
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		94
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT		2,210
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		1,596
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT		515
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT		63
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH		71
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH		5
78300100	PAVEMENT MARKING REMOVAL	SQ FT		506
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH		1
* 81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT		126
* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT		318
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT		166

\*SPECIALTY ITEMS  
 :) Non Participating Item (100% State)

FILE NAME = c:\pwwork\pwwid\HENSONKE\d0128026\p01708c\vr.dgn	USER NAME = hansonke	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>US RTE 30 SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 309	SECTION (20-1)M	COUNTY WHITESIDE	TOTAL SHEETS 53	SHEET NO. 3
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 64F37	
PLOT DATE = Wed Dec 02 10:06:55 2009	DATE -	REVISED -	REVISED -		ILLINOIS FED. AID PROJECT							