

SUMMARY OF QUANTITIES

paycode	description	units	quantity
50102400	CONCRETE REMOVAL	CU YD	55.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	55.3
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4880
50800515	BAR SPLICERS	EACH	62
52000110	PREFORMED JOINT STRIP SEAL	FOOT	404
52000365	NEOPRENE EXPANSION JOINT 6 1/2"	FOOT	69
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12510
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4170
70400100	TEMPORARY CONCRETE BARRIER	FOOT	912.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	912.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3240
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1150
Z0024476	FLEXIBLE DELINEATOR MAINTENANCE	EACH	100
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY ITEM