

SUMMARY OF QUANTITIES

80% FED.  
20% STATE  
NEW SN-050-2643

PAY CODE	DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE Y007
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	639
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	151
20101100	TREE TRUNK PROTECTION	EACH	10
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	9
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1
20200100	EARTH EXCAVATION	CU YD	710
20400800	FURNISHED EXCAVATION	CU YD	675
20700220	POROUS GRANULAR EMBANKMENT	CU YD	408
20800150	TRENCH BACKFILL	CU YD	359
* 25000300	SEEDING, CLASS 3	ACRE	0.75
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68
25100630	EROSION CONTROL BLANKET	SQ YD	2,864
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75
28000305	TEMPORARY DITCH CHECKS	FOOT	90
28000400	PERIMETER EROSION BARRIER	FOOT	136
28000500	INLET AND PIPE PROTECTION	EACH	1
28100109	STONE RIPRAP, CLASS A5	SQ YD	221
28200200	FILTER FABRIC	SQ YD	221
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	158
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	146
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	36
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	225
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.5
40600525	LEVELING BINDER (HAND METHOD), N50	TON	0.6
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	53
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	480
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	142
44000100	PAVEMENT REMOVAL	SQ YD	140
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	40
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,418
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50105200	REMOVE EXISTING CULVERTS	EACH	1

80% FED.  
20% STATE  
NEW SN-050-2643

PAY CODE	DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE Y007
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	163
50800105	REINFORCEMENT BARS	POUND	17,420
54003000	CONCRETE BOX CULVERTS	CU YD	87.1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	44
54213450	END SECTIONS 15"	EACH	2
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	23
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	248
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1
60236100	INLETS, TYPE A, TYPE 6 FRAME AND GRATE	EACH	2
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	425
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	50
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	306
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8
66700095	PERMANENT SURVEY MARKERS	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	60
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,200
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	50
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	759
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,200
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	50
* 78200405	GUARDRAIL MARKERS	EACH	28
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	175
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	127
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1
Z0054400	ROCK FILL	CU YD	160

\* SPECIALTY ITEM

PLAN SURVEYED \_\_\_\_\_ CHECKED \_\_\_\_\_  
ALIGNED \_\_\_\_\_ CHECKED \_\_\_\_\_  
NOTE BOOK \_\_\_\_\_  
NO. \_\_\_\_\_

PROFILE SURVEYED \_\_\_\_\_ CHECKED \_\_\_\_\_  
PLOTTED \_\_\_\_\_ CHECKED \_\_\_\_\_  
NOTE BOOK \_\_\_\_\_  
NO. \_\_\_\_\_