

SHORT-TERM PAVEMENT MARKING		
LOCATION	FOOT	NO. OF APPLICATIONS
JOBSITE	7,388.72	3
TOTAL	22,166 FOOT	

WORK ZONE PAVEMENT MARKING REMOVAL		
LOCATION	FOOT	WIDTH (IN)
JOBSITE	7,388.72	4
TOTAL	2,463 SQ FT	

URETHANE PAVEMENT MARKING SCHEDULE							
LOCATION	LETTERS & SYMBOLS, SPECIAL	LINE 4"		LINE 8"	LINE 12"		LINE 24"
		WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE
		SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT
JOBSITE	31.2	148,276	60,388	500	96	78	52
SUB-TOTAL	31	148,276	60,388	500	96	78	52
TOTAL	31	208,664		500	174		52

NOTE: PRIOR TO PLACING CENTERLINE STRIPING, CONTACT THE DISTRICT BUREAU OF OPERATIONS FOR A "NO PASSING ZONE" EVALUATION.

GUARDRAIL SCHEDULE								
LOCATION			GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	GUARDRAIL MARKERS, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL AGGREGATE EROSION CONTROL
STA.	TO	STA.	FOOT	FOOT	EACH	EACH	EACH	TON
RT. 79+48.00	TO	81+10.00	100		2	2	2	10.12
LT. 80+51.00	TO	81+99.00	100		2	2	2	10.12
RT. 176+78.00	TO	180+79.00	100		2	2	2	10.12
LT. 176+78.00	TO	182+26.00	100		2	2	2	10.12
LT. 224+57.00	TO	229+00.00	100		2	2	2	10.12
RT. 225+00.00	TO	229+73.00	100		2	2	2	10.12
RT. 322+36.00	TO	324+08.00	100		2	2	2	10.12
RT. 334+46.00	TO	336+01.00	100		2	2	2	10.12
LT. 335+15.00	TO	336+27.50	86	12.5	2	2	2	8.71
LT. 454+45.00	TO	455+51.00	100		2	2	2	10.12
RT. 454+45.00	TO	455+51.00	100		2	2	2	10.12
RT. 460+23.00	TO	460+73.00	50		1	1	1	5.06
LT. 460+11.00	TO	460+61.00	50		1	1	1	5.06
RT. 485+46.00	TO	490+06.00	100		2	2	2	10.12
TOTAL			1,286	13	26	26	26	130

TEMPORARY PAINT PAVEMENT MARKING SCHEDULE							
LOCATION	LETTERS & SYMBOLS, SPECIAL	LINE 4"		LINE 8"	LINE 12"		LINE 24"
		WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE
		SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT
JOBSITE	31.2	148,276	60,388	500	96	78	52
SUB-TOTAL	31	148,276	60,388	500	96	78	52
TOTAL	31	208,664		500	174		52