

CONSTRUCTING TEST STRIP	
LOCATION	40600895 EACH
ENTIRE PROJECT	1
<b>TOTAL</b>	<b>1</b>

MATERIAL TRANSFER DEVICE	
LOCATION	X0300729 TON
IL 17/91	7,784
IL17	9,111
<b>TOTAL</b>	<b>16,895</b>

SHOULDER RUMBLE STRIPS		
LOCATION STATION TO STATION	LENGTH FOOT	64200105 FOOT
IL 17/91		
RT STA 104+09.96 TO RT STA 112+12.29	802.33	802.33
RT STA 176+62.60 TO RT STA 185+49.10	886.50	886.50
LT STA 209+22.00 TO LT STA 220+84.30	1162.30	1162.30
IL 17		
RT STA 57+30 TO RT STA 67+20	990.00	990.00
<b>TOTAL</b>		<b>3,841</b>

MOWING	
LOCATION	X2503100 UNIT
ENTIRE PROJECT	670
<b>TOTAL</b>	<b>670</b>

AGGREGATE SHOULDER, TYPE B		
LOCATION STATION TO STATION	LENGTH FOOT	48101200 TON
IL 17/91		
LT&RT STA 00+39 TO STA 151+15.45	15,076.45	929
STA EQ 151+15.45 = 135+35.35		
LT&RT STA 135+35.35 TO STA 220+84.30	8,548.95	527
STA EQ 220+84.30 = 204+98.10		
LT&RT STA 204+98.10 TO STA 285+75	8,076.90	498
IL 17		
LT&RT STA 7+32 TO STA 346+94	33,962.00	2094
<b>TOTAL</b>		<b>4,048</b>

MOBILIZATION	
LOCATION	67100100 L SUM
ENTIRE PROJECT	1
<b>TOTAL</b>	<b>1</b>

TRAFFIC CONTROL SCHEDULE			
LOCATION	70100500 TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	70100480 TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	70100600 TRAFFIC CONTROL AND PROTECTION, STANDARD 701336
	L SUM	L SUM	L SUM
ENTIRE PROJECT	1	1	1
<b>TOTALS</b>	<b>1</b>	<b>1</b>	<b>1</b>

HOT-MIX ASPHALT SHOULDER, 8"		
LOCATION STATION TO STATION	AREA SQ FT	48203029 SQ YD
IL 17/91		
RT STA 104+09.96 TO RT STA 112+12.29	2406.99	267.4
RT STA 176+62.6 TO RT STA 177+62.6	300	33.3
LT STA 268+47.5 TO LT STA 272+57	1228.5	136.5
<b>TOTAL</b>		<b>437</b>

CLASS D PATCHES, 14 INCH			
LOCATION STATION TO STATION	44201815 TYPE II (SQ YD)	44201819 TYPE III (SQ YD)	44201821 TYPE IV (SQ YD)
IL 17/91			
STA 2+00 TO STA 151+15.45	109	17	29
STA EQ 151+15.45 = 135+35.35			
STA 135+35.35 TO STA 220+84.30	69		29
STA EQ 220+84.30 = 204+98.10			
STA 204+98.10 TO STA 285+70	35		29
IL 17			
FROM IL 17/91 W TO 1215 E RD	368		
FROM 1215 E RD TO 1300 E RD	267		
FROM 1300 E RD TO 1400 E RD	203		
FROM 1400 E RD TO 1500 E RD	240		
FROM 1500 E RD TO 1600 E RD	459		
FROM 1600 E RD TO IL 40	347		
<b>TOTALS</b>	<b>2,096</b>	<b>17</b>	<b>87</b>

PERMANENT SURVEY MARKERS	
LOCATION	66700095 EACH
ENTIRE PROJECT	12
<b>TOTAL</b>	<b>12</b>

PERMANENT SURVEY TIES	
LOCATION	66700605 EACH
ENTIRE PROJECT	48
<b>TOTAL</b>	<b>48</b>

PAVED SHOULDER REMOVAL		
LOCATION STATION TO STATION	AREA SQ FT	44004250 SQ YD
IL 17/91		
RT STA 104+09.96 TO RT STA 112+12.29	2,407	267.4
<b>TOTAL</b>		<b>267</b>

FILE NAME = D468747-shr-plan.dgn	USER NAME = mendezzj	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE = 12/7/2009	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
643	(11,12)RS-2;(6W)RS-3;(10)RS-4	STARK	45	14
CONTRACT NO. 68747			ILLINOIS FED. AID PROJECT	