

Short Term Pavement Marking							Work Zone Pavement Marking Removal
Location	Length	Dash	Shoulder	x2 Apps			
	Foot	Foot	Foot				
<b>Charter Oaks Structures</b>							
167+33.00 TO 168+33.00	100	10	8	36			6
Structure 072-0138	138	14	11	50			9
169+71.00 TO 170+71.00	100	10	8	36			6
167+39.00 TO 168+39.00	100	10	8	36			6
Structure 072-0139	126	13	10	45			8
169+65.00 TO 170+65.00	100	10	8	36			6
<b>I 74 / I 474 / IL 6 Structures</b>							
<b>Westbound</b>							
213+63.00 TO 214+62.31	99	10	8	36			6
Structure 072-0107	164	16	13	59			10
216+26.31 TO 217+68.00	142	14	11	51			9
Structure 072-0109	161	16	13	58			10
219+29.00 TO 220+30.00	101	10	8	36			7
<b>Eastbound</b>							
213+32.00 TO 214+56.31	124	12	10	45			8
Structure 072-0106	174	17	14	63			11
216+32.31 TO 217+65.00	133	13	11	48			8
Structure 072-0108	167	17	13	60			11
219+32.00 TO 220+32.00	100	10	8	36			6
Structure 072-0111	299	30	24	108			18
<b>Grand tota</b>	<b>2029</b>	<b>203</b>	<b>162</b>	<b>730</b>			<b>127</b>

Hot Mix Asphalt Removal (Deck)						
Structure #	CL Station	Length	Beg Sta	End Sta.	Width	Area
		FOOT			FOOT	SQ YD
072-0106	215+44.31	174	214+57.31	216+31.31	55	1063.3
072-0107	215+44.31	164	214+62.31	216+26.31	47.2	860.1
072-0108	218+48.50	167	217+65.00	219+32.00	53	983.4
072-0109	218+48.50	161	217+68.00	219+29.00	53.4	955.3
072-0111	512+13.50	299	513+63.00	510+64.00	42	1395.3
<b>Total</b>						<b>5257.5</b>

Hot Mix Asphalt Removal						
Structure #	CL Station	Length	Beg Sta	End Sta.	Width	Area
		FOOT			FOOT	SQ YD
072-0138	169+02.00	138	168+33.00	169+71.00	41.8	640.9
072-0139	169+02.00	126	168+39.00	169+65.00	41.8	585.2
<b>Total</b>						<b>1226.1</b>

Waterproofing Membrane System						
Structure #	CL Station	Length	Beg Sta	End Sta.	Width	Area
		FOOT			FOOT	SQ YD
072-0138	169+02.00	138	168+33.00	169+71.00	41.8	640.9
072-0139	169+02.00	126	168+39.00	169+65.00	41.8	585.2
<b>Total</b>						<b>1226.1</b>

ENGINEER'S FIELD OFFICE	
LOCATION	CAL MO
Jobsite	3
<b>TOTAL</b>	<b>3</b>

TRAFFIC CONTROL & PROTECTION 701401	
LOCATION	LSUM
Jobsite	1
<b>TOTAL</b>	<b>1</b>

MOBILIZATION	
LOCATION	L SUM
Jobsite	1
<b>TOTAL</b>	<b>1</b>

TRAFFIC CONTROL & PROTECTION 701406	
LOCATION	L SUM
Jobsite	1
<b>TOTAL</b>	<b>1</b>

MOWING	
LOCATION	UNIT
Jobsite	248
<b>TOTAL</b>	<b>248</b>

TRAFFIC CONTROL & PROTECTION 701411	
LOCATION	EACH
IL 6 / US 150	4
I 74 / I 474 / IL 6	6
<b>TOTAL</b>	<b>10</b>

CHANGABLE MESSAGE SIGN	
LOCATION	CAL DA
Jobsite	24
<b>TOTAL</b>	<b>24</b>

TRAFFIC CONTROL & PROTECTION 701446	
LOCATION	EACH
Jobsite	1
<b>TOTAL</b>	<b>1</b>

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	DAYS
Jobsite	10
<b>TOTAL</b>	<b>10</b>

TRAFFIC CONTROL & PROTECTION 701456	
LOCATION	L SUM
Jobsite	1
<b>TOTAL</b>	<b>1</b>