

**TEMPORARY PAVEMENT MARKING SCHEDULE**

LOCATION	LINE 4"						LINE 6"		LINE 8"	LINE 12"		LINE 24"
	SOLID - WHITE		SOLID - YELLOW		SKIP DASH - YELLOW		WHITE		WHITE	WHITE	YELLOW	FT
	EB/NB	WB/SB	EB/NB	WB/SB	EB/NB	WB/SB	EB/NB	WB/SB				
	FT		FT		FT				FT	FT		
<b>IL 17</b>												
<b>MARSHALL COUNTY</b>												
STA. 65+59	TO STA. 75+65	1,006	1,006									
STA. 75+65	TO STA. 77+14.37 BK	149	149	149			37					
STA. 18+12.54 AH	TO STA. 32+62	3,262	3,262	3,262			816					
STA. 32+62	TO STA. 48+62	1,600	1,600	1,600	1,600							
STA. 48+62	TO STA. 64+56	1,594	1,594		1,594	399						
STA. 64+56	TO STA. 454+05.39	38,949	38,949				9,737					
STA. 454+05.39	TO STA. 460+11	606	606	931	931						40	30
<b>IL 89</b>												
<b>PUTNAM COUNTY</b>												
STA. 562+00	TO STA. 570+50			850			212	850	850	964	753	120
STA. 570+50	TO STA. 572+08					40		158	158			
STA. 572+08	TO STA. 585+28				1,320	330		1,320	1,320			
STA. 585+28	TO STA. 596+90			1,162			290	1,162	1,162			
STA. 596+90	TO STA. 603+76					172		686	686			
STA. 603+76	TO STA. 611+15				739	185		739	739			
STA. 611+15	TO STA. 614+32					79		317	317			
STA. 614+32	TO STA. 619+83			551			138	551	551			
<b>MARSHALL COUNTY</b>												
STA. 619+83	TO STA. 622+24			241			60	241	241			
STA. 622+24	TO STA. 627+52					132		528	528			
STA. 627+52	TO STA. 640+72				1,320	330		1,320	1,320			
STA. 640+72	TO STA. 649+17			845	845			845	845			
STA. 649+17	TO STA. 661+84			1,267			317	1,267	1,267			
STA. 661+84	TO STA. 682+96					528		2,112	2,112			
STA. 682+96	TO STA. 693+52				1,056	264		1,056	1,056			
STA. 693+52	TO STA. 710+42			1,690	1,690			1,690	1,690			
STA. 710+42	TO STA. 719+92			950			238	950	950			
STA. 719+92	TO STA. 727+84				792	198		792	792			
STA. 727+84	TO STA. 751+60			2,376	2,376			2,376	2,376			
STA. 751+60	TO STA. 767+44			1,584			119	1,584	1,584			
STA. 767+44	TO STA. 788+03					515		2,059	2,059			
STA. 788+03	TO STA. 793+84				581	145		581	581			
STA. 793+84	TO STA. 799+12			528	528			528	528			
STA. 799+12	TO STA. 804+40			528			132	528	528			
STA. 804+40	TO STA. 826+58					554		2,218	2,218			
STA. 826+58	TO STA. 833+44				686	172		686	686			
STA. 833+44	TO STA. 836+08					66		264	264			
STA. 836+08	TO STA. 846+64			1,056			264	1,056	1,056			
STA. 846+64	TO STA. 891+52					1,122		4,488	4,488			
STA. 891+52	TO STA. 899+44				792	198		792	792			
STA. 899+44	TO STA. 910+00 BK			1,056			264	1,056	1,056			
STA. 39+80 AH	TO STA. 45+08.40					132		528	528			34
<b>IL 18</b>												
<b>PUTNAM COUNTY</b>												
STA. 425+95.50	TO STA. 430+15.00	420	420			105						
<b>SUB-TOTAL</b>		95,172		37,475		18,289		70,657		964	793	184
<b>TOTAL</b>				150,936				70,657		964	793	184

FILE NAME = 68915 - Phase 11.dgn  
 USER NAME = johnsonv  
 PLOT SCALE = 100.0000 / IN.  
 PLOT DATE = 12/5/2009

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

SCALE: SHEET NO. 3 OF 8 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698 649	123RS-4(122,124RS-5,2RS-3,3RS-4	MARSHALL PUTNAM	40	13
CONTRACT NO. 68915				
ILLINOIS FED. AID PROJECT				