

CULVERT SCHEDULE										
LOCATION	TYPE/SIZE	REINFORCEMENT BARS	EXPANSION BOLTS 3/4 IN X 15 INCH	CONCRETE COLLAR	REMOVE CONCRETE FLARED END SECTIONS	PRC FLARED END SECTIONS ARCH, EQRS 24"	GRATING FOR CONCRETE FLARED END SECTION EQRS 24"	GRATING FOR CONCRETE FLARED END SECTION EQRS 36"	DELINEATORS	PERIMETER EROSION BARRIER
		POUND	EACH	CU YD	EACH	EACH	EACH	EACH	EACH	FOOT
IL 17										
MARSHALL COUNTY										
LT. STA. 33+27.70	3 x 2 BOX							1		
RT. STA. 33+27.71								1		
LT. STA. 145+18.60	3 x 2 BOX							1	1	
RT. STA. 145+18.61								1	1	
LT. STA. 148+20.00	3 x 2 BOX							1		
RT. STA. 148+20.01								1		
LT. STA. 173+39.49	2 x 1.5 BOX						1			
RT. STA. 173+39.50								1		
LT. STA. 202+52.31	2 x 1.5 BOX						1			
RT. STA. 202+52.32								1		
LT. STA. 234+59.30	3 x 2 BOX							1		
RT. STA. 234+59.31								1	1	
LT. STA. 320+00.00	3 x 2 BOX							1	1	
RT. STA. 320+00.01								1	1	
LT. STA. 352+21.90	2 x 1.5 BOX						1			
RT. STA. 352+21.91			20	8	0.27	1	1	1	1	30
LT. STA. 373+74.59	2 x 1.5 BOX						1			
RT. STA. 373+74.60								1		
LT. STA. 442+09.69	2 x 1.5 BOX						1			
RT. STA. 442+09.70			20	8	0.27	1	1	1		30
SUBTOTAL		40	16	0.54	2	2	10	10	5	60
TOTAL		40	16	0.60	2	2	10	10	5	60

PRIME COAT CONVERSION FACTORS		
SURFACE TYPE	BIT PR COAT	AGG PR COAT
	(GAL/SQ YD)	(LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW HMA COURSES	0.03	2

HMA & AGGREGATE CONVERSION FACTORS		
SURFACE TYPE	LB	TON
	SQ YD IN	CU YD
HMA COURSES	112	2.016
COARSE AGGREGATE	114	2.05
FINE AGGREGATE		1.5

FILE NAME = 68915 - Phase II.dgn	USER NAME = johnsontv	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 8 OF 8 SHEETS STA. TO STA.

F.A.P. RTE. 689 649	SECTION 123RS-4, 122, 124RS-5, 2RS-3, 3RS-4	COUNTY MARSHALL PUTNAM	TOTAL SHEETS 40	SHEET NO. 18
CONTRACT NO. 68915			ILLINOIS FED. AID PROJECT	