

SCHEDULE OF QUANTITIES

PROTECTIVE COAT

LOCATION	SQYD
Parapet Walls (inside & top)	9
Joint Replacement Area	86
TOTAL	95

STRUCTURAL STEEL REPAIR

LOCATION	POUND
Span 7, Girder #1	150
TOTAL	150

ELASTOMERIC BEARING ASSEMBLY, TYPE I

LOCATION	EACH
Pier #3	5
Pier #6	5
TOTAL	10

T. C. & P STANDARD 701201

LOCATION	LSUM
Jobsite - SN.029-0050	1
TOTAL	1

CONCRETE REMOVAL

LOCATION	CUYD
Parapet and Joints	42.6
TOTAL	42.6

~~CLEANING & PAINTING STEEL BRIDGE~~

LOCATION	LSUM
Span 7, Girder #1	0.5
Joint #6 Beam Ends	0.5
TOTAL	1

ANCHOR BOLTS, 1"

LOCATION	EACH
Pier #3	10
Pier #6	10
TOTAL	20

TEMPORARY BRIDGE TRAFFIC SIGNALS

LOCATION	EACH
Jobsite - SN.029-0050	1
TOTAL	1

CONCRETE SUPERSTRUCTURE

LOCATION	CUYD
Parapets and Joints	43
TOTAL	43

REINFORCEMENT BARS, EPOXY COATED

LOCATION	POUND
Joints at both Abuts & Piers #3 and #6	6640
TOTAL	6640

MOBILIZATION

LOCATION	LSUM
Jobsite - SN.029-0050	1
TOTAL	1

TEMPORARY RUMBLE STRIP

LOCATION	EACH
Jobsite - SN.029-0050	2
TOTAL	2

JACK & REMOVE EXISTING BEARINGS

LOCATION	EACH
Joints #3 and #6	10
TOTAL	10

BAR SPLICERS

LOCATION	EACH
Approach	6
Deck	48
TOTAL	54

T. C. & P STANDARD 701321

LOCATION	EACH
Jobsite - SN.029-0050	1
TOTAL	1

CHANGEABLE MESSAGE SIGN

LOCATION	CALMO
Jobsite - SN.029-0050	2
TOTAL	2

△ Rev. 2-19-10

SN.029-0050 IL.116
over Spoon Riv.

S:\VIEW\G067\T03\SN.029-0050\BRIDGE CONTRACT\QUANTITIES\BRIDGE SN.029-0050\IL.116-SpoonRiv.dgn