

SUMMARY OF QUANTITIES

100% STATE SAFETY-2A FULTON COUNTY

100% STATE SAFETY-2A FULTON COUNTY

CODE NO.	ITEM	UNIT	RURAL	TOTAL
50300300	PROTECTIVE COAT	SQYD	95	95
50102400	CONCRETE REMOVAL	CUYD	42.6	42.6
50300255	CONCRETE SUPERSTRUCTURE	CUYD	43	43
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	10	10
50501130	STRUCTURAL STEEL REPAIR	POUND	150	150
50600300	CLEANING AND PAINTING STEEL BRIDGE	LSUM	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6640	6640
50800515	BAR SPLICERS	EACH	54	54
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	10	10
52100520	ANCHOR BOLTS, 1"	EACH	20	20
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106800	CHANGEABLE MESSAGE SIGN	CALMO	2	2
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	4591	4591
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	1530	1530
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1133	1133
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1109	1109
* 78005110	EPOXY MARKING - LINE 4"	FOOT	2788	2788
78300105	PAVEMENT MARKING REMOVAL	FOOT	2788	2788
X0325216	THERMAL SPRAYING (METALIZING) PPC BEAM ENDS	SQFT	961	961

CODE NO.	ITEM	UNIT	RURAL	TOTAL
X0325218	BLAST CLEANING PPC BEAM ENDS	FOOT	60	60
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQFT	174	174
X5080600	MECHANICAL SPLICERS	EACH	20	20
* X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	148.7	148.7
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQYD	7	7
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	3	3

*SPECIALTY ITEM

Rev. 2-19-10

SN.029-0050 IL.116
over Spoon Riv.

FILE NAME = SN.029-0050 IL.116SovrSpoonRiv.WD DrainEx.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ---
		DRAWN - CEJ	REVISED - ---
	PLOT SCALE = 1/83.7051' / IN.	CHECKED - ---	REVISED - ---
	PLOT DATE = 12/3/2009	DATE - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 665	SECTION (142-BR)	COUNTY FULTON	TOTAL SHEETS 25	SHEET NO. 3
SUPERSTRUCTURE REPAIRS			CONTRACT NO. 68925	
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

S:\GEN\DRFT\ASTOS\PLNS\SDUAD14\BRIDGE CONTRACTS\JOINTS\89925 SN.029-0050 IL.116SovrSpoonRiv.dgn

SCHEDULE OF QUANTITIES

PROTECTIVE COAT

LOCATION	SQYD
Parapet Walls (inside & top)	9
Joint Replacement Area	86
TOTAL	95

STRUCTURAL STEEL REPAIR

LOCATION	POUND
Span 7, Girder #1	150
TOTAL	150

ELASTOMERIC BEARING ASSEMBLY, TYPE I

LOCATION	EACH
Pier #3	5
Pier #6	5
TOTAL	10

T. C. & P STANDARD 701201

LOCATION	LSUM
Jobsite - SN.029-0050	1
TOTAL	1

CONCRETE REMOVAL

LOCATION	CUYD
Parapet and Joints	42.6
TOTAL	42.6

~~CLEANING & PAINTING STEEL BRIDGE~~

LOCATION	LSUM
Span 7, Girder #1	0.5
Joint #6 Beam Ends	0.5
TOTAL	1

ANCHOR BOLTS, 1"

LOCATION	EACH
Pier #3	10
Pier #6	10
TOTAL	20

TEMPORARY BRIDGE TRAFFIC SIGNALS

LOCATION	EACH
Jobsite - SN.029-0050	1
TOTAL	1

CONCRETE SUPERSTRUCTURE

LOCATION	CUYD
Parapets and Joints	43
TOTAL	43

REINFORCEMENT BARS, EPOXY COATED

LOCATION	POUND
Joints at both Abuts & Piers #3 and #6	6640
TOTAL	6640

MOBILIZATION

LOCATION	LSUM
Jobsite - SN.029-0050	1
TOTAL	1

TEMPORARY RUMBLE STRIP

LOCATION	EACH
Jobsite - SN.029-0050	2
TOTAL	2

JACK & REMOVE EXISTING BEARINGS

LOCATION	EACH
Joints #3 and #6	10
TOTAL	10

BAR SPLICERS

LOCATION	EACH
Approach Deck	6
	48
TOTAL	54

T. C. & P STANDARD 701321

LOCATION	EACH
Jobsite - SN.029-0050	1
TOTAL	1

CHANGEABLE MESSAGE SIGN

LOCATION	CALMO
Jobsite - SN.029-0050	2
TOTAL	2

△ Rev. 2-19-10

S:\VIEW\GAP\T\STDS\PLANS\504014\BRIDGE CONTRACT\QUANTITIES\68925 SN.029-0050 IL.116 SpoonRiv.dgn

FILE NAME SN.029-0050 IL.116 SpoonRiv.dgn	USER NAME Jonasco	DESIGNED CEJ	DRAWN CEJ	CHECKED ---	DATE ---	REVISED ---	REVISED ---	REVISED ---	REVISED ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	F.A.P. RTE. 665 SECTION (142-BR) COUNTY FULTON TOTAL SHEETS 25 SHEET NO. 4 SUPERSTRUCTURE REPAIRS CONTRACT NO. 68925 ILLINOIS FED. AID PROJECT
--	----------------------	-----------------	--------------	----------------	-------------	----------------	----------------	----------------	----------------	---	-------------------------------	--------------	---------------------------------	--------------------------	---

SN.029-0050 IL.116
over Spoon Riv.