

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- * BDE Form 2289 (Environmental Survey Request)
- * A location map showing the size limits and location of the use area
- * Signed property owner agreement form-D4 PI0100
- * Color photographs depicting the use area
- * Borrow Area Entry Agreement form-D4 PI0101

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

JOB SPECIFIC NOTES

If it is necessary to remove railing near parapet removal area the railing shall be removed, salvaged, and replaced according to Section 509.05 of the Standard Specifications. Cost to be included in Concrete Superstructure.

S:\GEN\DRFT\STDS\PLNS\SD\LD\14\BRIDGE CONTRACTS\JOINTS\68925 SN.029-0050 IL.116\over-SpoonRiv.dgn

SN.029-0050 IL.116
over Spoon Riv.

FILE NAME = SN.029-0050 IL.116\over-SpoonRiv.WO DrnsExt.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMMITMENTS & GENERAL NOTES	F.A.P. RTE. 665	SECTION (142-BR)	COUNTY FULTON	TOTAL SHEETS 25	SHEET NO. 2
	PLOT SCALE = 183.7091' / IN.	CHECKED - ---	REVISED - ---		SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____	SUPERSTRUCTURE REPAIRS CONTRACT NO. 68925				
	PLOT DATE = 12/1/2009	DATE - ---	REVISED - ---			FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				