

SCHEDULE OF QUANTITIES

PROTECTIVE COAT

LOCATION	SQYD
Parapet Walls (inside & top)	9
Joint Replacement Area	86
TOTAL	95

STRUCTURAL STEEL REPAIR

LOCATION	POUND
Span 7, Girder #1	150
TOTAL	150

ELASTOMERIC BEARING ASSEMBLY, TYPE I

LOCATION	EACH
Pier #3	5
Pier #6	5
TOTAL	10

T, C, & P STANDARD 701201

LOCATION	LSUM
Jobsite - SN.029-0050	1
TOTAL	1

CONCRETE REMOVAL

LOCATION	CUYD
Parapet and Joints	42.6
TOTAL	42.6

CLEANING & PAINTING STEEL BRIDGE

LOCATION	LSUM
Span 7, Girder #1	0.5
Joint #6 Beam Ends	0.5
TOTAL	1

ANCHOR BOLTS, 1"

LOCATION	EACH
Pier #3	10
Pier #6	10
TOTAL	20

TEMPORARY BRIDGE TRAFFIC SIGNALS

LOCATION	EACH
Jobsite - SN.029-0050	1
TOTAL	1

CONCRETE SUPERSTRUCTURE

LOCATION	CUYD
Parapets and Joints	43
TOTAL	43

REINFORCEMENT BARS, EPOXY COATED

LOCATION	POUND
Joints at both Abuts & Piers #3 and #6	6640
TOTAL	6640

MOBILIZATION

LOCATION	LSUM
Jobsite - SN.029-0050	1
TOTAL	1

TEMPORARY RUMBLE STRIP

LOCATION	EACH
Jobsite - SN.029-0050	2
TOTAL	2

JACK & REMOVE EXISTING BEARINGS

LOCATION	EACH
Joints #3 and #6	10
TOTAL	10

BAR SPLICERS

LOCATION	EACH
Approach	6
Deck	48
TOTAL	54

T, C, & P STANDARD 701321

LOCATION	EACH
Jobsite - SN.029-0050	1
TOTAL	1

CHANGEABLE MESSAGE SIGN

LOCATION	CALMO
Jobsite - SN.029-0050	2
TOTAL	2

S:\GEN\DRFT\STDS\KAL\NS\DU\AD\1\BRIDGE CONTRACTS\JOINTS\68925 SN.029-0050\IL.116\over Spoon Riv.dgn

FILE NAME =	USER NAME = Jonesco	DESIGNED - CEJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
SN.029-0050 IL.116over Spoon Riv.40 Drawn		DRAWN - CEJ	REVISED -			665	1142-BR1	FULTON	25	4	
PLOT SCALE = 1/8" = 1' / 1/4"		CHECKED -	REVISED -			SUPERSTRUCTURE REPAIRS		CONTRACT NO. 68925			
PLOT DATE = 12/4/2009		DATE -	REVISED -			FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT					

SN.029-0050 IL.116
over Spoon Riv.