

SCHEDULE OF QUANTITIES

PAVEMENT MARKING TAPE, TYPE III, 4"

LOCATION	FOOT
Work Area & TCB Tapers	4591
TOTAL	4591

EPOXY MARKING LINE, 4"

LOCATION	FOOT
Jobsite Deck Surface	2788
TOTAL	2788

STRUCTURAL REPAIR OF CONCRETE =< 5"

LOCATION	SQFT
Pier #3 & #6 PPC Beam Ends	174
TOTAL	174

DECK SLAB REPAIR (PARTIAL)

LOCATION	SQYD
Bridge Deck Surface	7
TOTAL	7

WORKZONE PAVEMENT MARKING REMOVAL

LOCATION	SOFT
Work Area & TCB Tapers	1530
TOTAL	1530

PAVEMENT MARKING REMOVAL

LOCATION	FOOT
Jobsite Deck Surface	2788
TOTAL	2788

MECHANICAL SPLICERS

LOCATION	EACH
Pier #3 (PPC I-Beam Span)	20
TOTAL	20

IMPACT ATTENUATORS, TEMPORARY NRD, TL3

LOCATION	FOOT
Jobsite-SN.029-0050	2
TOTAL	2

* TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
Jobsite - SN.029-0050	1064
TOTAL	1064

THERMAL SPRAYING (METALIZING) PPC BEAM ENDS

LOCATION	SQFT
Pier #3 & #6 PPC Beam Ends	961
TOTAL	961

WIDTH RESTRICTION SIGNING

LOCATION	LSUM
Traffic Control Placement	1
TOTAL	1

IMPACT ATTENUATORS, RELOCATE NRD, TL3

LOCATION	FOOT
Jobsite-SN.029-0050	2
TOTAL	2

* RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
Jobsite - SN.029-0050	992
TOTAL	992

BLAST CLEANING PPC BEAM ENDS

LOCATION	FOOT
Pier #3 & #6 PPC Beam Ends	60
TOTAL	60

STRIP SEAL EXPANSION JOINT ASSEMBLY

LOCATION	FOOT
Four Joint Repl.- SN. 029-0050	148.7
TOTAL	148.7

* QUANTITIES MAY BE REVERSED IF
CONSTRUCTION STAGES ARE SWITCHED.

S:\GEN\DRAWING\STIPES\PLANS\SPRUE\4-BRIDGE CONTRACTS\JOINTS\ABR25 SN.029-0050\ABR25-0050 IL.116\SPRUE.dgn

FILE NAME = SN.029-0050 IL.116 over Spoon Riv. MD Drawn	USER NAME = jonesce	DESIGNED - CEJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE. 665	SECTION (142-BR1)	COUNTY FULTON	TOTAL SHEETS 25	SHEET NO. 5
PLOT SCALE = 1/8" = 1' IN. PLOT DATE = 12/4/2009				DRAWN - CEJ CHECKED - DATE -		SUPERSTRUCTURE REPAIRS CONTRACT NO. 68925		FEDERAL ROAD DIST. NO. 4 (ILLINOIS) FED. AID PROJECT		

SN.029-0050 IL.116
over Spoon Riv.