

SUMMARY OF QUANTITIES

		100% STATE SAFETY-2A WOODFORD COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
20200500	EARTH EXCAVATION (WIDENING)	CUYD	57	57
35650400	BASE COURSE WIDENING 9"	SOYD	227	227
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	15	15
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	22	22
50300300	PROTECTIVE COAT	SOYD	327	327
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	261	261
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2	2
50102400	CONCRETE REMOVAL	CUYD	13.5	13.5
50300255	CONCRETE SUPERSTRUCTURE	CUYD	13.6	13.6
50300260	BRIDGE DECK GROOVING	SOYD	258	258
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1480	1480
50800515	BAR SPLICERS	EACH	17	17
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	88	88
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	14	14
70106800	CHANGEABLE MESSAGE SIGN	CALMO	6	6
* 70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	2114	2114
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SOFT	705	705
70400100	TEMPORARY CONCRETE BARRIER	FOOT	322	322
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	298	298
78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	1290	1290

		100% STATE SAFETY-2A WOODFORD COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
78300105	PAVEMENT MARKING REMOVAL	FOOT	1290	1290
X0325216	THERMAL SPRAYING (METALIZING) PPC BEAM ENDS	SOFT	414	414
X0325218	BLAST CLEANING PPC BEAM ENDS	FOOT	40	40
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SOFT	18	18
* X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	36	36
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SOYD	261	261
40600990	TEMPORARY RAMP	SQ YD	36	36
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	261	261
Z0020800	EROSION CONTROL CURB	FOOT	925	925
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
X0320887	POLYMER CONCRETE	CU FT	1.7	1.7

*SPECIALTY ITEM

S:\GEN\DRFT\STR&LNS\S04014\BRIDGE CONTRACT\JOINTS\JOINTS_JOINTS.dgn 11/17/09 11:17 AM

FILE NAME = IL117ovr.M11Ck.dgn
 USER NAME = jonesc
 PLOT SCALE = 103.9676 / IN.
 PLOT DATE = 12/17/2009

DESIGNED - CEJ	REVISED - ---
DRAWN - CEJ	REVISED - ---
CHECKED - ---	REVISED - ---
DATE - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 702	SECTION (114BR-1)J	COUNTY WOODFORD	TOTAL SHEETS 23	SHEET NO. 3
MISC. BRIDGE REPAIRS		CONTRACT NO. 68928		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SN. 102-0041 IL117 ovr
MILL CRK. S. of US24