

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-30)RA-1-2	CHAMPAIGN	119	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

TABULATION OF CLASS B PATCHING 10"									
			44200970	44200974	44200976				
	CADD	2% OF TOTAL	CL B PTCH T II, 10"	CL B PTCH T III, 10"	CL B PTCH T IV, 10"	Z0017100 DOWEL	44213200 SAW CUTS	Z0075300 TIE BARS	44213100 PAVEMENT FABRIC
LOCATION	SQ YD	SQ YD	15% OF TOTAL SQ YD	60% OF TOTAL SQ YD	25% OF TOTAL SQ YD	BARS EACH	FOOT	EACH	SQ YD
NB ENTR/ EXIT RAMPS	3843.0	76.9							
SB ENTR/ EXIT RAMPS	3563.0	71.3							
SB TRUCK PARKING LOT	6129.0	122.6							
<b>TOTAL =</b>	<b>13535.0</b>	<b>270.7</b>	<b>40.6</b>	<b>162.4</b>	<b>67.7</b>	<b>602.0</b>	<b>1462.0</b>	<b>100.0</b>	<b>270.7</b>
<b>USE =</b>	<b>13535.0</b>	<b>271.0</b>	<b>41.0</b>	<b>162.0</b>	<b>68.0</b>	<b>602.0</b>	<b>1462.0</b>	<b>100.0</b>	<b>271.0</b>

THE PATCHING QUANTITIES REPRESENT AND ESTIMATE OF CLASS B PATCHING 10" BASED ON 2% OF THE TOTAL SQUARE YARDAGE OF THE AREAS ABOVE. THESE AREAS WERE MEASURED IN CADD.

TABULATION OF CLASS B PATCHING 8"									
			44200934	44200942	44200944				
	CADD	2% OF TOTAL	CL B PTCH T II, 8"	CL B PTCH T III, 8"	CL B PTCH T IV, 8"	Z0017100 DOWEL	44213200 SAW CUTS	Z0075300 TIE BARS	44213100 PAVEMENT FABRIC
LOCATION	SQ YD	SQ YD	15% OF TOTAL SQ YD	60% OF TOTAL SQ YD	25% OF TOTAL SQ YD	BARS EACH	FOOT	EACH	SQ YD
NB CAR PARKING LOT & RAMPS	2458.4	49.2							
SB CAR PARKING LOT & RAMPS	2366.0	47.3							
<b>TOTAL =</b>	<b>4824.4</b>	<b>96.5</b>	<b>14.5</b>	<b>57.9</b>	<b>24.1</b>	<b>214.0</b>	<b>521.2</b>	<b>50.0</b>	<b>96.5</b>
<b>USE =</b>	<b>4824.0</b>	<b>97.0</b>	<b>15.0</b>	<b>58.0</b>	<b>24.0</b>	<b>214.0</b>	<b>521.0</b>	<b>50.0</b>	<b>97.0</b>

THE PATCHING QUANTITIES REPRESENT AND ESTIMATE OF CLASS B PATCHING 8" BASED ON 2% OF THE TOTAL SQUARE YARDAGE OF THE AREAS ABOVE. THESE AREAS WERE MEASURED IN CADD.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF PATCHING**

SCALE: VERT. / HORIZ. DATE

DRAWN BY / CHECKED BY