



LEGEND

- PAY LIMITS OF POROUS GRANULAR EMBANKMENT - CA-6
- POROUS GRANULAR MATERIAL - CA-7 (6") INCLUDED IN PAY ITEM FOR BOX CULVERT

DRAWING NOT TO SCALE

GENERAL NOTES

- 1) SN 021-8055 SHALL BE CONSTRUCTED ON A 20 DEGREE SKEW LEFT FORWARD. THE DIMENSIONS SHOWN IN THIS DETAIL ARE PERPENDICULAR TO THE CENTERLINE OF THE BOX CULVERT. THE STATIONS ALONG THE CENTERLINE OF ROUTE 133 WILL VARY.
- 2) WORK SHOWN IN THE DETAIL SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE PORTIONS OF SECTION 207 AND SECTION 540 OF THE STANDARD SPECIFICATIONS.
- 3) POROUS GRANULAR EMBANKMENT SHALL EXTEND 2 FT. BEYOND THE HMA SHOULDER.
- 4) THIS WORK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR POROUS GRANULAR EMBANKMENT.
- 5) THE AREA TO BE EXCAVATED FOR THE PROPOSED BOX CULVERT SHALL BE MEASURED AND PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR STRUCTURE EXCAVATION.

•DOUGLAS & MOULTRIE

FILE NAME =	USER NAME = bowerml	DESIGNED - <i>MLB</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	POROUS GRANULAR EMBANKMENT PAY LIMITS STATION 2+48.30, SN 021-8055	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\PWIDOT\BOWERML\dms85036\70234\deta1s.dgn	DRAWN - <i>MLB</i>	REVIS	REVIS			749	120RS-3	*	55	34	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVIS	REVIS			CONTRACT NO. 70234					
PLOT DATE = 12/4/2009	DATE - 10/27/09	REVIS	REVIS			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.		