

LOCATION OF WORK:

DOUGLAS CO. RURAL RDWY IMPRVMNTS FAI-57 STA. 547+00.00 TO STA. 848+62.49 90% FED 10% STATE	CHAMPAIGN CO. RURAL RDWY IMPRVMNTS FAI-57 STA. 848+62.49 TO STA. 350+00.00 90% FED 10% STATE	DOUGLAS CO. RURAL MINOR STR. REPAIRS FAI-57 SN 021-2010 SN 021-2011 90% FED 10% STATE X081-2A	CHAMPAIGN CO. RURAL MINOR STR. REPAIRS FAI-57 SN 010-0198 SN 010-0199 90% FED 10% STATE X271-2A
---	---	---	---

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	DOUGLAS CO. 1000	CHAMPAIGN CO. 1000
20400800	FURNISHED EXCAVATION	CU YD	460.0	230.0	230.0
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	960.0	660.0	300.0
35101400	AGGREGATE BASE COURSE, TYPE B	TON	59.0	46.0	13.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	67,843.0	34,198.5	33,644.5
40600300	AGGREGATE (PRIME COAT)	TON	1,357.0	683.9	673.1
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	297.0		297.0
40600895	CONSTRUCTING TEST STRIP	EACH	3.0	1.5	1.5
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,620.0	886.7	3,733.3
40600990	TEMPORARY RAMP	SQ YD	4,406.0	1,631.7	2,774.3
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	25,320.0		25,320.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	31,743.0	15,010.1	16,732.9
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	76.0	35.5	40.5
40800030	AGGREGATE (PRIME COAT)	TON	2.0	0.7	1.3
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	153.0	74.5	78.5
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4,899.0	2,943.0	1,956.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	63,609.0		63,609.0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	4,121.0		4,121.0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	175,555.0	83,752.4	91,802.6
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	3,045.0		3,045.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	92,698.0	70,078.1	22,619.9
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	3,668.0	3,668.0	
44200561	CLASS A PATCHES, TYPE I, 11 INCH	SQ YD	239.0	239.0	

* SPECIALTY ITEM(S)

CONT'D NEXT SHEET

* CHAMPAIGN & DOUGLAS

FILE NAME = c:\pw\work\PWID001\SHERERJM\0134546\05	USER NAME = shererjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JMS	REVISED -					57	(21-28,21-10-29,10-30)RS-1	*	115	5
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -		SCALE: SHEET NO. 1 OF 5 SHEETS STA. TO STA.			CONTRACT NO. 70251				
	PLOT DATE = 12/14/2009	DATE - 111309	REVISED -		ILLINOIS FED. AID PROJECT							