

48203100 HOT MIX ASPHALT SHOULDERS

				LENGTH	WIDTH	AREA	SHOULDER	48203100	40600100	40600300
				(FOOT)	(FOOT)	(SQ YD)	THICKNESS	HMA SHLD	BIT MATLS	AGG PR CT
STATION	TO	STATION					(INCHES)	(TON)	(GAL)	(TONS)
I-57 MAINLINE (DOUGLAS)										
LT SB	547+01.25	LT SB	553+92.12	690.9	10	787.6	1.5	64.5	76.8	1.5
RT SB	547+01.25	RT SB	553+92.12	690.9	6	460.6	1.75	45.1	46.1	0.9
LT NB	547+01.25	LT NB	553+92.12	690.9	6	460.6	1.75	45.1	46.1	0.9
RT NB	320+10.98	RT NB	327+03.10	692.1	6	461.4	1.5	38.8	46.1	0.9
LT SB	556+91.12	LT SB	560+95.93	404.8	10	449.8	1.5	37.8	45.0	0.9
RT SB	556+91.12	RT SB	560+95.93	404.8	6	269.9	1.75	26.4	27.0	0.5
LT NB	556+91.12	LT NB	560+45.13	354.0	6	236.0	1.75	23.1	23.6	0.5
RT NB	556+91.12	RT NB	560+45.13	354.0	10	393.3	1.5	33.0	39.3	0.8
LT SB	563+55.29	LT SB	575+43.68	1188.4	10	1320.4	1.5	110.9	132.0	2.6
RT SB	563+55.29	RT SB	575+43.68	1188.4	6	792.3	1.75	77.6	79.2	1.6
LT SB	575+43.98	LT SB	580+22.18	478.2	10	531.3	1.5	44.6	53.1	1.1
RT SB	575+43.98	RT SB	580+22.18	478.2	6	318.8	1.75	31.2	31.9	0.6
LT SB	580+22.18	LT SB	583+97.18	375.0	10	416.7	1.5	35.0	41.7	0.8
RT SB	580+22.18	RT SB	583+97.18	375.0	6	250.0	1.5	21.0	25.0	0.5
LT NB	563+05.65	LT NB	575+43.68	1238.0	6	825.4	1.75	80.9	82.5	1.7
RT NB	563+05.65	RT NB	575+43.68	1238.0	10	1375.6	1.5	115.5	137.6	2.8
LT NB	575+43.98	LT NB	580+22.18	478.2	6	318.8	1.75	31.2	31.9	0.6
LT NB	580+22.18	LT NB	583+97.18	375.0	6	250.0	1.5	21.0	25.0	0.5
RT NB	575+43.98	RT NB	580+22.18	478.2	10	531.3	1.5	44.6	53.1	1.1
RT NB	580+22.18	RT NB	583+97.18	375.0	10	416.7	1.5	35.0	41.7	0.8
LT SB	583+97.18	LT SB	686+68.32	10271.1	10	11412.4	1.5	958.6	1141.2	22.8
LT SB	686+68.32	LT SB	689+46.05	277.7	10	308.6	1.5	25.9	30.9	0.6
RT SB	583+97.18	RT SB	686+68.32	10271.1	6	684.7	1.75	671.0	684.7	13.7
RT SB	686+68.32	RT SB	689+46.05	277.7	6	185.2	1.5	15.6	18.5	0.4
LT NB	583+97.18	LT NB	686+68.32	10271.1	6	684.7	1.75	671.0	684.7	13.7
LT NB	686+68.32	LT NB	689+46.05	277.7	6	185.2	1.5	15.6	18.5	0.4
RT NB	583+97.18	RT NB	686+68.32	10271.1	10	11412.4	1.5	958.6	1141.2	22.8
RT NB	686+68.32	RT NB	689+46.05	277.7	10	308.6	1.5	25.9	30.9	0.6
LT SB	689+46.05	LT SB	736+24.61	4678.6	10	5198.4	1.5	436.7	519.8	10.4
RT SB	689+46.05	RT SB	736+24.61	4678.6	6	3119.0	1.75	305.7	311.9	6.2
LT SB	736+26.44	LT SB	791+00.00	5473.6	10	6081.7	1.5	510.9	608.2	12.2
RT SB	736+26.44	RT SB	791+00.00	5473.6	6	3649.0	1.75	357.6	364.9	7.3
LT SB	791+02.19	LT SB	791+67.85	65.7	10	73.0	1.5	6.1	7.3	0.1
LT SB	791+67.85	LT SB	794+42.85	275.0	10	305.6	1.5	25.7	30.6	0.6
RT SB	791+02.19	RT SB	791+67.85	65.7	6	43.8	1.75	4.3	4.4	0.1
RT SB	791+67.85	RT SB	794+42.85	275.0	6	183.3	1.5	15.4	18.3	0.4
LT NB	689+46.05	LT NB	736+24.61	4678.6	6	3119.0	1.75	305.7	311.9	6.2
RT NB	689+46.05	RT NB	736+24.61	4678.6	10	5198.4	1.5	436.7	519.8	10.4
LT NB	736+26.44	LT NB	791+00.00	5473.6	6	3649.0	1.75	357.6	364.9	7.3
RT NB	736+26.44	RT NB	791+00.00	5473.6	10	6081.7	1.5	510.9	608.2	12.2
LT NB	791+02.19	LT NB	791+67.85	65.7	6	43.8	1.75	4.3	4.4	0.1
LT NB	791+67.85	LT NB	794+42.85	275.0	6	183.3	1.5	15.4	18.3	0.4
RT NB	791+02.19	RT NB	791+67.85	65.7	10	73.0	1.5	6.1	7.3	0.1
RT NB	791+67.85	RT NB	794+42.85	275.0	10	305.6	1.5	25.7	30.6	0.6
LT SB	794+42.85	LT SB	843+84.01	4941.2	10	5490.2	1.5	461.2	549.0	11.0
RT SB	794+42.85	RT SB	843+84.01	4941.2	6	3294.1	1.75	322.8	329.4	6.6
LT SB	843+85.95	LT SB	848+62.49	476.5	10	529.5	1.5	44.5	52.9	1.1
RT SB	843+85.95	RT SB	848+62.49	476.5	6	317.7	1.75	31.1	31.8	0.6
LT NB	794+42.85	LT NB	843+84.01	4941.2	6	3294.1	1.75	322.8	329.4	6.6
RT NB	794+42.85	RT NB	843+84.01	4941.2	10	5490.2	1.5	461.2	549.0	11.0
LT NB	843+85.95	LT NB	848+62.49	476.5	6	317.7	1.75	31.1	31.8	0.6
RT NB	843+85.95	RT NB	848+62.49	476.5	10	529.5	1.5	44.5	52.9	1.1

SUB-TOTAL = 9,348.8 10,492.4 209.8

(CONTD NEXT SHEET)

• CHAMPAIGN & DOUGLAS

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\SHERRERJM\d0134546\0570251-shr-schedules.dgn	DRAWN - N/A	REVISED -			57	(21-28,21-10-29,10-30)RS-1	*	115	26	CONTRACT NO. 70251		
PLOT SCALE = 100.0000' / IN.	CHECKED - N/A	REVISED -			SCALE: N/A	SHEET NO. 7 OF 16 SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT		
PLOT DATE = 12/4/2009	DATE - 110509	REVISED -										