

SCHEDULE OF CLASS A PATCHING (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200561 TYPE I 11.0" (sq. yd)	44200565 TYPE II 11.0" (sq. yd)	44200569 TYPE III 11.0" (sq. yd)	44200571 TYPE IV 11.0" (sq. yd)	44213200 SAW CUTS (ft)	Z0075300 TIE BARS (each)	44213000 PATCHING REINFORCEMENT (sq. yd)
I-57 MAINLINE (DOUGLAS)											
775+55.00	NB	DL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0
799+10.00	NB	DL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0
799+10.00	NB	PL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0
802+01.00	NB	DL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0
839+83.00	NB	DL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0
839+83.00	NB	PL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0
861+80.00	NB	DL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0
861+93.00	NB	DL	8	12	0.0	10.7	0.0	0.0	64.0	0.0	10.7
864+61.00	NB	DL	8	12	0.0	10.7	0.0	0.0	64.0	0.0	10.7
864+61.00	NB	PL	8	12	0.0	10.7	0.0	0.0	64.0	0.0	10.7
883+40.00	NB	DL	8	12	0.0	10.7	0.0	0.0	64.0	0.0	10.7
932+50.00	NB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
932+61.00	NB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
932+80.00	NB	PL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
874+82.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
848+01.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
842+42.00	SB	DL	10	6	0.0	6.7	0.0	0.0	44.0	0.0	6.7
792+50.00	SB	DL	25	6	0.0	0.0	16.7	0.0	74.0	13.0	16.7
754+12.00	SB	PL	8	12	0.0	10.7	0.0	0.0	64.0	0.0	10.7
733+03.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
732+84.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
732+06.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
731+55.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
730+55.00	SB	DL	14	6	0.0	9.3	0.0	0.0	52.0	0.0	9.3
729+08.00	SB	DL	14	6	0.0	9.3	0.0	0.0	52.0	0.0	9.3
728+80.00	SB	DL	10	6	0.0	6.7	0.0	0.0	44.0	0.0	6.7
722+75.00	SB	DL	12	6	0.0	8.0	0.0	0.0	48.0	0.0	8.0
722+44.00	SB	DL	12	6	0.0	8.0	0.0	0.0	48.0	0.0	8.0
722+02.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0
721+90.00	SB	DL	12	6	0.0	8.0	0.0	0.0	48.0	0.0	8.0
SUB-TOTAL =					40.0	165.3	16.7	0.0	1510.0	13.0	222.0

• CHAMPAIGN & DOUGLAS

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF PATCHING			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\PWIDOT\SHERRJ\034546\0570251-shr-schedules.dgn	DRAWN - N/A	CHECKED - N/A	REVISED -		57	(21-28,21-10-29,10-30)RS-1	*	115	39				
PLOT SCALE = 100.0000' / IN.	DATE - 110509	REVISOR -	REVISOR -		SCALE: N/A			SHEET NO. 4 OF 9 SHEETS		STA.	TO STA.	CONTRACT NO. 70251	
PLOT DATE = 12/11/2009					ILLINOIS FED. AID PROJECT								