

SCHEDULE OF CLASS A PATCHING (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200561	44200565	44200569	44200571	44213200	Z0075300	44213000	
					TYPE I 11.0" (sq. yd)	TYPE II 11.0" (sq. yd)	TYPE III 11.0" (sq. yd)	TYPE IV 11.0" (sq. yd)	SAW CUTS (ft)	TIE BARS (each)	PATCHING REINFORCEMENT (sq. yd)	
I-57 MAINLINE (DOUGLAS)												
712+00.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
710+93.00	SB	DL	16	6	0.0	10.7	0.0	0.0	56.0	0.0	10.7	
707+44.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
706+67.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
703+69.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
703+53.00	SB	DL	20	6	0.0	13.3	0.0	0.0	64.0	10.0	13.3	
703+35.00	SB	DL	8	6	0.0	5.3	0.0	0.0	40.0	0.0	5.3	
686+55.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
645+98.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
633+60.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
624+64.00	SB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0.0	4.0	
564+10.00	SB	PL	6	12	0.0	8.0	0.0	0.0	60.0	0.0	8.0	
563+96.00	SB	DL	16	12	0.0	0.0	21.3	0.0	80.0	0.0	21.3	
560+56.00	SB	PL	8	12	0.0	10.7	0.0	0.0	64.0	0.0	10.7	
560+27.00	SB	DL	10	12	0.0	13.3	0.0	0.0	68.0	0.0	13.3	
548+47.00	SB	DL	8	6	0.0	5.3	0.0	0.0	40.0	0.0	5.3	
SUB-TOTAL =					32.0	66.7	21.3	0.0	760.0	10.0	120.0	
TOTAL =					238.7	558.7	95.3	95.6	6452.0	118.0	988.2	
USE =					239.0	559.0	95.0	96.0	6452.0	118.0	988.0	

• CHAMPAIGN & DOUGLAS

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF PATCHING			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\PWIDOT\SHERERJM\d0134546\0570251-shr-schedules.dgn	DRAWN - N/A	REVISIONS	REVISED -					57	(21-28,21-10-29,10-30)RS-1	*	115	40	
	PLOT SCALE = 100.0000' / IN.	CHECKED - N/A	REVISED -		SCALE: N/A			SHEET NO. 5 OF 9 SHEETS		STA.	TO STA.	CONTRACT NO. 70251	
	PLOT DATE = 12/11/2009	DATE - 110509	REVISED -		ILLINOIS FED. AID PROJECT								