

**78000600 THERMOPLASTIC PAVEMENT MARKING, LINE 12"
YELLOW - DIAGONAL MEDIAN**

STATION	TO	STATION	FOOT
618+89		621+09	37.0
9+36		9+58	21.0

TOTAL = 58.0

**78000650 THERMOPLASTIC PAVEMENT MARKING, LINE 24"
WHITE - STOP BARS**

	STATION	TYPE	FOOT
EB	453+73	SOLID	53.0
WB	454+73	SOLID	58.0
HENNING RD.	6+37	SOLID	32.0
SOUTH			
HENNING RD.	7+58	SOLID	28.0
NORTH			
EB	622+09	SOLID	36.0
WB	187+03	SOLID	24.0
LOGAN AVE.	9+55		25.0
SOUTH			
LOGAN AVE.	10+55	SOLID	33.0
NORTH			

TOTAL = 289.0

70300100 SHORT TERM PAVEMENT MARKING

	STATION	TO	STATION	MILLING	BINDER	SURFACE	TOTAL
EB	396+77.00		447+82.84	510.6	0.0	510.6	1021.2
WB	396+77.00		447+82.84	510.6	0.0	510.6	1021.2
EB	447+82.84		622+89.31	1750.6	1750.6	1750.6	5251.8
WB	447+82.84		622+89.31	1750.6	1750.6	1750.6	5251.8
EB	186+81.78		188+46.00	16.4	16.4	16.4	49.2
WB	186+81.78		188+46.00	16.4	16.4	16.4	49.2
HENNING RD./EB	450+31.00		453+73.00	34.2	34.2	34.2	102.6
	450+31.00		453+73.00	34.2	34.2	34.2	102.6
HENNING RD./WB	454+73.00		458+41.00	36.8	36.8	36.8	110.4
	454+73.00		458+41.00	36.8	36.8	36.8	110.4
LOGAN AVE./EB	621+09.00		622+09.00	10.0	10.0	10.0	30.0
	187+03.00		187+63.00	6.0	6.0	6.0	18.0

TOTAL = 13118.5

USE = 13119.0

70301000 WORKZONE PAVEMENT MARKING REMOVAL

	STATION	TO	STATION	SURFACE (FOOT)	REMOVAL (SQ FT)
EB	396+77.00		447+82.84	510.6	170.2
WB	396+77.00		447+82.84	510.6	170.2
EB	447+82.84		622+89.31	1750.6	583.5
WB	447+82.84		622+89.31	1750.6	583.5
EB	186+81.78		188+46.00	16.4	5.5
WB	186+81.78		188+46.00	16.4	5.5
HENNING RD./EB	450+31.00		453+73.00	34.2	11.4
	450+31.00		453+73.00	34.2	11.4
HENNING RD./WB	454+73.00		458+41.00	36.8	12.3
	454+73.00		458+41.00	36.8	12.3
LOGAN AVE./EB	621+09.00		622+09.00	10.0	3.3
	187+03.00		187+63.00	6	2.0

TOTAL = 1571.1

USE = 1571.0

*FAU 7052 / FAP 729

FILE NAME =	USER NAME = bucklesJJ	DESIGNED - RLA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\BUCKLESJJ\d0132727\0970315-sht-schedule.dgn	DRAWN - RLA	REVISED -	*				(36X,36X-1,34Z-3)RS-1	VERMILION	58	34	
PLOT SCALE = 40.0000' / IN.	CHECKED - JMS	REVISED -	SCALE: SHEET NO. 8 OF 8 SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT				
PLOT DATE = 12/7/2009	DATE - 7/6/2009	REVISED -	CONTRACT NO. 70315								