

CODE NO	ITEM	UNIT	TOTAL QUANTITY	FAS - RURAL TWO LANE 100% STATE 1000	Parking Lanes '100% VILLAGE
20200100	EARTH EXCAVATION	CU YD	34.0	34.0	
20400800	FURNISHED EXCAVATION	CU YD	32.0	32.0	
20800150	TRENCH BACKFILL	CU YD	3.0	3.0	
*25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23.0	23.0	
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23.0	23.0	
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23.0	23.0	
25100630	EROSION CONTROL BLANKET	SQ YD	570.0	570.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25.00	25.00	
28000305	TEMPORARY DITCH CHECKS	FOOT	24.0	24.0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13,239.0	13,057.0	182.0
40600300	AGGREGATE (PRIME COAT)	TON	265.0	262.0	3.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	3,355.0	3,355.0	
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,919.0	2,919.0	
40600990	TEMPORARY RAMP	SQ YD	351.0	351.0	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7,558.0	7,405.0	153.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	292.0	292.0	
40800030	AGGREGATE (PRIME COAT)	TON	6.0	6.0	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	300.0	300.0	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	11,750.0	9,932.0	1,818.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	79,875.0	79,875.0	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	624.0	624.0	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	48.0	48.0	
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	38.0	38.0	
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	16.0	16.0	
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SQ YD	8.0	8.0	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	857.0	857.0	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	139.0	139.0	
50105220	PIPE CULVERT REMOVAL	FOOT	40.0	40.0	
54213450	END SECTIONS 15"	EACH	2.0	2.0	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	41.0	41.0	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4.0	4.0	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5.0	5.0	
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	338.0	338.0	
*63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	100.0	100.0	
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75.0	75.0	
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	1.0	1.0	
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	3.0	3.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.0	3.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	

Y025

CODE NO	ITEM	UNIT	TOTAL QUANTITY	FAS - RURAL TWO LANE 100% STATE 1000	Parking lanes '100% VILLAGE
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9,962.0	9,962.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,151.0	1,151.0	
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	81,620.0	81,620.0	
*78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	109.0	109.0	
*78200405	GUARDRAIL MARKERS	EACH	9.0	9.0	
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0	4.0	
X0301232	SURVEY MARKER VAULT	EACH	4.0	4.0	
XZ193300	SURVEY MARKER, TYPE 1(SPECIAL)	EACH	20.0	20.0	

Y025

FILE NAME =	USER NAME = ptersonbr	DESIGNED -	REVISED -
c:\pw_work\PIW1001\PIERSONBR\d0115438\05	0523-zht-gemnote.dgn	DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/4/2009	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2466	(9,10,11)RS-3	McLean	47	3
CONTRACT NO. 70523			ILLINOIS FED. AID PROJECT	