

SUMMARY OF QUANTITIES

LOCATION:

FAP 760 (IL 48) FAP 760 (IL 48)
 PIATT CTY DEWITT CTY
 STA. 856+04.00 STA. 1138+57.8
 TO TO
 STA. 1138+57.8 246+85.2138+57.8
 RURAL RURAL
 TWO LANE TWO LANE
 100% STATE 100% STATE

CONSTRUCTION CODE:

I000 I000

PAY ITEM CODE	PAY ITEM	UNIT	TOTAL	QTY	QTY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12,976.0	9,547.0	3,429.0
40600300	AGGREGATE (PRIME COAT)	TON	50.0	36.1	13.9
40800990	TEMPORARY RAMP	SQYD	232.0	188.0	44.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10,900.0	8,019.0	2,881.0
44000155	HOT-Mix ASPHALT SURFACE REMOVAL, 1 1/2"	SQYD	129,783.0	95,464.0	34,319.0
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQYD	5.0	0.0	5.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQYD	90.0	81.0	9.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,995.0	1,426.0	569.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2.0	1.4	0.6
67100100	MOBILIZATION	LSUM	1.0	0.7	0.3
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1.0	0.7	0.3
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1.0	0.7	0.3
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,035.0	5,709.0	2,326.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQFT	1,340.0	952.0	388.0
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	94.0	94.0	0.0
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	315.0	315.0	0.0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	222.0	222.0	0.0
78000850	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	132.0	60.0	72.0
78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	102,713.0	26,164.0	76,549.0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	515.0	366.0	149.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	515.0	366.0	149.0
X4401705	PARTIAL DEPTH REMOVAL	SQYD	368.0	247.0	121.0
X4421000	PARTIAL DEPTH PATCHING	TON	145.0	97.0	48.0
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	7.0	5.0	2.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = leroyma	DESIGNED -	REVISED -
c:\pe_work\pilot\leroy\12270\0570	59-sh1-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/2/2009	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
760	124RS-6&125RS-3	*	15	4
DEWITT & PIATT			CONTRACT NO. 70759	
ILLINOIS FED. AID PROJECT				