

40300602

SEAL COAT AGGREGATE, SPECIAL

	LOCATION	OFFSET	WIDTH	TONS
LT. & RT.	268+13.80 TO 282+74.43	9.0'	2.0'	6.5
LT. & RT.	282+74.43 TO 309+08.95	9.0'	2.0'	11.7
LT. & RT.	309+08.95 TO 323+57.45	* VARIES	2.0'	6.4
LT. & RT.	323+57.45 TO 326+71.43	9.0' & VAR.	2.0'	1.4
LT. & RT.	326+71.43 TO 493+78.43	9.0'	2.0'	74.30
	493+78.43 TO 494+89.57	BRIDGE OMISSION		
LT. & RT.	494+89.57 TO 502+88.00	9.0'	2.0'	3.5
LT. & RT.	502+88 TO 503+12	CULVERT OMISSION		
LT. & RT.	503+12.00 TO 517+81.00	9.0'	2.0'	6.5
	517+81 TO 519+03			
LT. & RT.	519+03.00 TO 557+64.00	9.0'	2.0'	17.2
	557+64 TO 557+98	CULVERT OMISSION		
LT. & RT.	557+98.00 TO 677+38.26	9.0'	2.0'	53.10
	677+38.26 TO 678+45.74	BRIDGE OMISSION		
LT. & RT.	678+45.74 TO 719+36.00	9.0'	2.0'	18.2
	719+36 TO 719+64	CULVERT OMISSION		
LT. & RT.	719+64.00 TO 828+74.00			24.20
	828+74 TO 830+56	BRIDGE OMISSION		
LT. & RT.	830+56.00 TO 856+25.71	9.0'	2.0'	5.7
	856+25.71 = DOUGLAS / EDGAR CO. LINE			
LT. & RT.	856+25.71 TO 932+29.05	9.0'	2.0'	16.90
* - VERIFY IN FIELD		TOTAL	TONS	246.0

X4032500

BITUMINOUS MATERIALS (COVER & SEAL COATS) SPECIAL

	LOCATION	OFFSET	WIDTH	GAL.
LT. & RT.	268+13.80 TO 282+74.43	9.0'	2.0'	194.75
LT. & RT.	282+74.43 TO 309+08.95	9.0'	2.0'	351.27
LT. & RT.	309+08.95 TO 323+57.45	* VARIES	2.0'	193.13
LT. & RT.	323+57.45 TO 326+71.43	9.0' & VAR.	2.0'	41.87
LT. & RT.	326+71.43 TO 493+78.43	9.0'	2.0'	2,222.76
	493+78.43 TO 494+89.57	BRIDGE OMISSION		
LT. & RT.	494+89.57 TO 502+88.00	9.0'	2.0'	106.46
LT. & RT.	502+88 TO 503+12	CULVERT OMISSION		
LT. & RT.	503+12.00 TO 517+81.00	9.0'	2.0'	195.87
	517+81 TO 519+03			
LT. & RT.	519+03.00 TO 557+64.00	9.0'	2.0'	514.8
	557+64 TO 557+98	CULVERT OMISSION		
LT. & RT.	557+98.00 TO 677+38.26	9.0'	2.0'	1,592.03
	677+38.26 TO 678+45.74	BRIDGE OMISSION		
LT. & RT.	678+45.74 TO 719+36.00	9.0'	2.0'	545.37
	719+36 TO 719+64	CULVERT OMISSION		
LT. & RT.	719+64.00 TO 828+74.00			1,454.67
	828+74 TO 830+56	BRIDGE OMISSION		
LT. & RT.	830+56.00 TO 856+25.71	9.0'	2.0'	342.63
	856+25.71 = DOUGLAS / EDGAR CO. LINE			
LT. & RT.	856+25.71 TO 932+29.05	9.0'	2.0'	1,013.78
* - VERIFY IN FIELD		TOTAL	GALLONS	8769.39

78001110

PAINT PAVEMENT MARKING LINE - 4"

LOCATION	4" WHITE FEET	4" YELLOW FEET	
268+13.80 - 282+74.43 = THERMOPLASTIC			
LT. & RT. 282+74.43-310+03	5,457.14	682.14	
310+03 TO 323+68.26 = BRIDGE OMISSION			
LT. & RT. 323+68.26 - 493+78.43	34,020.34	4,252.54	
493+78.43 TO 494+89.57 = BRIDGE OMISSION			
LT. & RT. 494+89.57 - 517+81.00	4,582.86	572.86	
517+81 TO 519+03 = BRIDGE OMISSION			
LT. & RT. 519+03.00 - 677+38.26	31,670.52	3,958.82	
677+38.26 TO 678+45.74 = BRIDGE OMISSION			
LT. & RT. 678+45.74 - 752+82.30	14,873.12	1,859.14	
752+82.30 TO 768+83.70 = THERMOPLASTIC			
LT. & RT. 768+83.70 - 828+74.00	11,980.60	1,497.58	
828+74.00 TO 830+56.00 = BRIDGE OMISSION			
LT. & RT. 830+56.00 - 856+25.71	5,139.42	642.43	
EDGAR CO. LINE = 856+25.71			
LT. & RT. 856+25.71 - 932+29.05	15,206.68	1,900.84	
NO PASSING ZONES			
W.B. 282+74 - 286+48		374	
E.B. 306+56 - 310+03		347	
W.B. 323+02.67 - 332+12.75		910.1	
E.B. 747+08 - 752+85		577	
E.B. & W.B. 768+83.7 - 776+61		1,554.60	
E.B. 776+60.91 - 787+27.18		1,066.30	
E.B. 926+16.05 - 929+86.05		370	
TOTALS	122,930.68	20,565.35	143,496.03

XZ193300

PERMANENT SURVEY MARKERS, TYPE 1 (SPECIAL)

METRIC STATION	ENGLISH STATION	EACH	DESCRIPTION
254+27.69	273+90.85	1	P.O.T.
270+19.90	326+14.64	1	P.I.
347+18.63	578+72.94	1	P.I.
396+95.89	742+02.55	1	P.O.T.
000+00.00	856+25.71	1	P.O.T.
022+72.15	930+80.28	1	P.C.
TOTAL =		6	EACH

• DOUGLAS & EDGAR

FILE NAME =	USER NAME = shererjm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwwork\p\WIDOT\SHERERJM\d0115071\70760Schedules.dgn	DRAWN -	REVISED -	323			(145,146)RS-3 & 147RS-5	*	27	16	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 70760							
PLOT DATE = 11/27/2009	DATE -	REVISED -	SCALE:			SHEET NO. 4 OF 5 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		