

LOCATION OF WORK:				FAI 57 URBAN CHAMPAIGN COUNTY STA 1270+24.74 TO STA 1292+37.60 100% STATE	FAI 57 RURAL CHAMPAIGN COUNTY STA 1292+37.60 TO STA 1649+71.37 100% STATE	FAI 57 RURAL CHAMPAIGN COUNTY IMPACT ATTENUATOR IMPROVEMENTS 100% STATE	FAI 57 RURAL CHAMPAIGN COUNTY S.N. 010-0082 100% STATE	FAI 57 RURAL CHAMPAIGN COUNTY S.N. 010-8311 S.N. 010-8312 100% STATE
CONSTRUCTION TYPE CODE:				I000	I000	SFTY-3N	SFTY-2A	SFTY-2A
CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
X4420118	CLASS A PATCH (SPECIAL)	SQ YD	246.0	46.0	200.0	0.0	0.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	32180.0	1654.0	30526.0	0.0	0.0	0.0
40600300	AGGREGATE (PRIME COAT)	TON	644.0	34.0	610.0	0.0	0.0	0.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	1.0	1.0	0.0	0.0	0.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1755.0	1172.0	583.0	0.0	0.0	0.0
40600990	TEMPORARY RAMP	SQ YD	3275.0	187.0	3088.0	0.0	0.0	0.0
40603525	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N105	TON	16875.0	902.0	15958.0	0.0	0.0	15.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	17166.0	902.0	16249.0	0.0	0.0	15.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	22.0	0.0	22.0	0.0	0.0	0.0
40800030	AGGREGATE (PRIME COAT)	TON	1.0	0.0	1.0	0.0	0.0	0.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	25.0	0.0	25.0	0.0	0.0	0.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	203342.0	10736.0	192606.0	0.0	0.0	0.0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	1067.0	0.0	1067.0	0.0	0.0	0.0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	4267.0	0.0	4267.0	0.0	0.0	0.0
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	175.5	0.0	0.0	0.0	0.0	175.5
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	221.0	0.0	221.0	0.0	0.0	0.0
44213000	PATCHING REINFORCEMENT	SQ YD	467.0	46.0	421.0	0.0	0.0	0.0
44213200	SAW CUTS	FOOT	2910.0	288.0	2622.0	0.0	0.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3519.0	201.0	3318.0	0.0	0.0	0.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	10040.0	572.0	9468.0	0.0	0.0	0.0
50157300	PROTECTIVE SHIELD	SQ YD	250.0	0.0	0.0	0.0	250.0	0.0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1410.0	0.0	0.0	0.0	1410.0	0.0
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	8.0	0.0	0.0	0.0	8.0	0.0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	8.0	0.0	0.0	0.0	8.0	0.0
52100520	ANCHOR BOLTS, 1"	EACH	16.0	0.0	0.0	0.0	16.0	0.0
60260100	INLETS TO BE ADJUSTED	EACH	2.0	2.0	0.0	0.0	0.0	0.0
63400105	GUARD POSTS	EACH	50.0	0.0	50.0	0.0	0.0	0.0
63400205	GUARD POSTS REMOVAL	EACH	37.0	0.0	37.0	0.0	0.0	0.0

FILE NAME =	USER NAME = bowerm	DESIGNED - MLB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\p101dot\bowern\10023\70766	S00.dgn	DRAWN - MLB	REVISED -					57	10-37RS-2&10,27-30RS	CHAMPAIGN	41	5
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -		SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. TO STA.			CONTRACT NO. 70766				
	PLOT DATE = 12/2/2009	DATE - 02-24-09	REVISED -		ILLINOIS FED. AID PROJECT							