

PERFORMED PLASTIC PAVEMENT MARKING TYPE B (INLAID) - LINE 5"		
LOCATION	QUANTITY LENGTH (FOOT)	MARKING TYPE (P. P. M. TYB)
SANGAMON COUNTY (IL 125 / IL 123 INTERSECTION)		
IL 123	50	30' SKIP - 10' DASH CENTERLINE, YELLOW
T.R. 22 (YANKEE TOWN RD.)	50	30' SKIP - 10' DASH CENTERLINE, YELLOW
GRAND TOTAL =		100

PERFORMED PLASTIC PAVEMENT MARKING TYPE B (INLAID) - LINE 6"		
LOCATION	QUANTITY LENGTH (FOOT)	MARKING TYPE (P. P. M. TYB)
SANGAMON COUNTY (IL 125 / IL 123 INTERSECTION)		
156+50.00 TO 158+90.00 (LEFT TURN LANE, EASTBOUND)	60	6' SKIP - 2' DASH
158+90.00 TO 161+30.00 (LEFT TURN LANE, EASTBOUND)	240	SOLID LANE LINE
162+26.11 TO 163+41.11 (LEFT TURN LANE, WESTBOUND)	115	SOLID LANE LINE
163+41.11 TO 165+21.11 (LEFT TURN LANE, WESTBOUND)	45	6' SKIP - 2' DASH
GRAND TOTAL =		460 FEET

RAISED REFLECTIVE PAVEMENT MARKERS				
LOCATION	DISTANCE (FEET)	QUANTITY (EACH, @ 80' CTRS.)	MARKER TYPE	
CASS COUNTY				
STATION TO STATION				
1079+00.00	1099+98.54	2099	26	TWO-WAY AMBER, 80' CTRS.
STATION EQUATION:				
1099+98.54 (BK) = 18+36.74 (AHEAD)				
18+36.74	24+57.24	621	8	TWO-WAY AMBER, 80' CTRS.
SUB TOTAL =			34	
CASS / SANGAMON COUNTY LINE = STA. 24+57.24				
SANGAMON COUNTY				
24+57.24	152+50.00	12793	160	TWO-WAY AMBER, 80' CTRS.
152+50.00	169+21.00	1671	52	TWO-WAY AMBER, 40' & 80' CTRS.
169+21.00	276+50.00	10729	134	TWO-WAY AMBER, 80' CTRS.
SUB TOTAL =			346	
152+50.00	169+21.00	1671	11	ONE-WAY CRYSTAL
SUB TOTAL =			11	
GRAND TOTAL =			391	

THERMOPLASTIC PAVEMENT MARKING - LINE 8"		
LOCATION	QUANTITY LENGTH (FOOT)	MARKING TYPE (THERMOPLASTIC)
SANGAMON COUNTY (IL 125 / IL 123 INTERSECTION)		
NORTHWEST ISLAND	220	ISLAND OUTLINE
SOUTHWEST ISLAND	120	ISLAND OUTLINE
GRAND TOTAL =		340 FEET

PERFORMED PLASTIC PAVEMENT MARKING TYPE B (INLAID) - LINE 24"		
LOCATION	QUANTITY LENGTH (FOOT)	MARKING TYPE (P. P. M. TYB)
SANGAMON COUNTY (IL 125 / IL 123 INTERSECTION)		
IL 123, SOUTHBOUND THRU LANE	12	STOP BAR
IL 123, SOUTHBOUND RIGHT TURN LANE	18	STOP BAR
YANKEETOWN RD., NORTHBOUND THRU LANE	23	STOP BAR
GRAND TOTAL =		53

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B, (INLAID) - LETTERS & SYMBOLS		
LOCATION	QUANTITY (SQ FT)	MARKING TYPE (P. P. M. TYB)
SANGAMON COUNTY (IL 125 / IL 123 INTERSECTION)		
STA. 158+90	15.6	LEFT TURN ARROW, WHITE
STA. 159+95	15.6	LEFT TURN ARROW, WHITE
STA. 161+00	15.6	LEFT TURN ARROW, WHITE
STA. 162+56	15.6	LEFT TURN ARROW, WHITE
STA. 163+41	15.6	LEFT TURN ARROW, WHITE
GRAND TOTAL =		78.0 SQ FT

THERMOPLASTIC PAVEMENT MARKING - LINE 12"			
LOCATION	QUANTITY LENGTH (FOOT)	MARKING TYPE (THERMOPLASTIC)	
SANGAMON COUNTY (IL 125 / IL 123 INTERSECTION)			
STATION TO STATION			
153+50.00	158+90.00	115	45° MEDIAN DIAGONAL
163+41.11	168+00.00	92	45° MEDIAN DIAGONAL
NORTHWEST ISLAND		93	45° ISLAND DIAGONAL
SOUTHWEST ISLAND		43	45° ISLAND DIAGONAL
GRAND TOTAL =		343 FEET	

IL 125/IL 123 INTERSECTION		
LOCATION	PIPE CULVERT REMOVAL (FOOT)	PIPE CULVERTS, CLASS C, TYPE 1 12" (FOOT)
YANKEE TOWN ROAD		
STA. 8+09.66 LT	20	30

IL 125 / IL 123 INTERSECTION ISLAND QUANTITIES						
LOCATION	PAVEMENT REMOVAL (SQ FT)	CONCRETE MEDIAN SURFACE REMOVAL (SQ FT)	COMBINATION CONCRETE CURB & GUTTER REMOVAL (FOOT)	CONCRETE MEDIAN SURFACE, 4" (SQ FT)	COMB. CONC. CURB & GUTTER TYPE M-4.06 (FOOT)	COMB. CONC. CURB & GUTTER TYPE M-4.24 (FOOT)
STA. 161+50.00 LEFT	31	96	60	162	23	43

FILE NAME =	USER NAME = coxte	DESIGNED - RTS	REVISED -
es:\pwwork\PWIDOT\COXTE\dma84394\ahht-schedule.dgn		DRAWN - RTS	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED - RTS	REVISED -
PLOT DATE = Dec-18-2009 04:48:15PM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
SCALE:	SHEET NO. 6 OF 6 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	105(RS-6), 106(RS-4)	SANG./CASS	88	19
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				